

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT				
<b>APPLICATION FOR PERMIT TO DRILL</b>						1. WELL NAME and NUMBER Taylor 3-9C4				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT ALTAMONT				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR EP ENERGY E&P COMPANY, L.P.						7. OPERATOR PHONE 713 997-5038				
8. ADDRESS OF OPERATOR 1001 Louisiana, Houston, TX, 77002						9. OPERATOR E-MAIL maria.gomez@epenergy.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) Fee			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Randy J. and Sadie M. Taylor						14. SURFACE OWNER PHONE (if box 12 = 'fee') 435-823-5502				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') P.O. Box 941, Duchesne, UT 84021						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		900 FSL 1750 FEL		SWSE	9	3.0 S	4.0 W	U		
Top of Uppermost Producing Zone		900 FSL 1750 FEL		SWSE	9	3.0 S	4.0 W	U		
At Total Depth		900 FSL 1750 FEL		SWSE	9	3.0 S	4.0 W	U		
21. COUNTY DUCHESNE			22. DISTANCE TO NEAREST LEASE LINE (Feet) 900			23. NUMBER OF ACRES IN DRILLING UNIT 640				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 2300			26. PROPOSED DEPTH MD: 12200 TVD: 12200				
27. ELEVATION - GROUND LEVEL 5999			28. BOND NUMBER 400JU0708			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE Duchesne City				
<b>Hole, Casing, and Cement Information</b>										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
COND	20	13.375	0 - 600	54.5	J-55 LT&C	8.8	Class G	758	1.15	15.8
SURF	12.25	9.625	0 - 4450	40.0	N-80 LT&C	9.5	35/65 Poz	650	3.16	11.0
							Premium Lite High Strength	191	1.33	14.2
I1	8.75	7	0 - 9250	29.0	P-110 LT&C	10.5	Premium Lite High Strength	306	2.31	12.0
							Premium Lite High Strength	91	1.91	12.5
L1	6.125	4.5	9050 - 12200	13.5	P-110 LT&C	12.0	50/50 Poz	232	1.61	12.3
<b>ATTACHMENTS</b>										
<b>VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES</b>										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Maria S. Gomez				TITLE Principal Regulatory Analyst				PHONE 713 997-5038		
SIGNATURE				DATE 01/08/2013				EMAIL maria.gomez@epenergy.com		
API NUMBER ASSIGNED 43013519540000				APPROVAL  Permit Manager						

**Taylor 3-9C4  
Sec. 9, T3S, R4W  
DUCHESNE COUNTY, UT**

**EP ENERGY E&P COMPANY, L.P.**

**DRILLING PROGRAM**

**1. Estimated Tops of Important Geologic Markers**

<u>Formation</u>	<u>Depth</u>
Green River (GRRV)	4,416'
Green River (GRTN1)	5,196'
Mahogany Bench	6,136'
L. Green River	7,416'
Wasatch	9,281'
T.D. (Permit)	12,200'

**2. Estimated Depths of Anticipated Water, Oil, Gas or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Green River (GRRV)	4,416'
	Green River (GRTN1)	5,196'
	Mahogany Bench	6,136'
Oil	L. Green River	7,416'
Oil	Wasatch	9,281'

**3. Pressure Control Equipment: (Schematic Attached)**

A 4.5" by 20.0" rotating head on structural pipe from surface to 600'. A 4.5" by 13 3/8" Smith Rotating Head and 5M Annular from 600' to 4,450' on Conductor. A 5M BOP stack, 5M Annular, and 5M kill lines and choke manifold used from 4,450' to 9,250'. A 10M BOE w/rotating head, 5M annular, blind rams & mud cross from 9,250' to TD. The BOPE and related equipment will meet the requirements of the 5M and 10M system.

**OPERATORS MINIMUM SPECIFICATIONS FOR BOPE:**

The surface casing will be equipped with a flanged casing head of 5M psi working pressure. An 11" 5M x 11" 10M spool, 11" x 10M psi BOP and 5M psi Annular will be nipped up on the surface casing and tested to 250 psi low test / 3,000 psi high test for 10 minutes each prior to drilling out. The surface casing will be tested to 1,000 psi. for 30 mins. Intermediate casing will be tested to the greater of 1500 psi or 0.22 psi/ft. The choke manifold equipment, upper Kelly cock, floor safety valves will be tested to 5M psi. The annular preventer will be tested to 250 psi low test and 4,000 psi high test. The 10M BOP will be installed

with 3 ½" pipe rams, blind rams, mud cross and rotating head from intermediate shoe to TD. The BOPE will be hydraulically operated.

In addition, the BOP equipment will be tested after running intermediate casing, after any repairs to the equipment and at least once every 30 days. Pipe and blind rams will be activated on each trip, annular preventer will be activated weekly and weekly BOP drills will be held with each crew.

**Statement on Accumulator System and Location of Hydraulic Controls:**

Precision Rig # 404 is expected to be used to drill the proposed well. Operations will commence after approval of this application. Manual and/or hydraulic controls will be in compliance with 5M and 10M psi systems.

**Auxiliary Equipment:**

- A) Pason monitoring systems with gas monitor 600' – TD.
- B) Mud logger with gas monitor – 4,450' to TD
- C) Choke manifold with one manual and one hydraulic operated choke
- D) Full opening floor valve with drill pipe thread
- E) Upper and lower Kelly cock
- F) Shaker, de-sander and de-silter, and centrifuge.

**4. Proposed Casing & Cementing Program:**

Please refer to the attached Wellbore Diagram.

All casing will meet or exceed the following design safety factors:

- Burst = 1.00
- Collapse = 1.125
- Tension = 1.2 (including 100k# overpull)

Cement design calculations will be based on: 25% excess over gauge hole in the liner section, 10% excess over gauge hole in the intermediate section, and 75% excess on the lead and 50% excess on the tail over gauge hole volume for the surface hole. Actual volumes pumped will be a minimum of the volumes stated above, however, actual hole size will be based on caliper logs in the liner and intermediate sections. Gauge hole will be used for the surface section.

**5. Drilling Fluids Program:**

Proposed Mud Program:

Interval	Type	Mud Weight
Surface	WBM	8.8 – 9.5
Intermediate	WBM	9.5 – 10.5
Production	WBM	10.5 – 12.0

Anticipated mud weights are based on actual offset well bottom-hole pressure data. Mud weights utilized may be somewhat higher to allow for trip margin and to provide hole stability for running logs and casing.

Visual mud monitoring equipment will be utilized.

6. **Evaluation Program:**

Logs:

Mud Log: 4,450' - TD.

Open Hole Logs: Gamma Ray, Neutron-Density, Resistivity, Sonic, from base of surface casing to TD.

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 12,200' TD equals approximately 7,613 psi. This is calculated based on a 0.624 psi/foot gradient (12.0 ppg mud density at TD).

Maximum anticipated surface pressure equals approximately 4,929 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/ft).

Maximum anticipated surface pressure based on frac gradient at 7" casing shoe is 0.8 psi/ft at 9,250' = 7,400 psi

BOPE and casing design will be based on the lesser of the two MASPs which is 4,929 psi.


8. **OPERATOR REQUESTS THAT THE PROPOSED WELL BE PLACED ON CONFIDENTIAL STATUS.**





## Drilling Schematic

Company Name: <b>EP ENERGY</b>	Date: January 3, 2012
Well Name: <b>Taylor 3-9C4</b>	TD: 12,200
Field, County, State: <b>Altamont - Bluebell, Duchesne, Utah</b>	AFE #:
Surface Location: <b>Sec 9 T3S R4W 900' FSL 1750' FEL</b>	BHL: <b>Straight Hole</b>
Objective Zone(s): <b>Green River, Wasatch</b>	Elevation: <b>5999</b>
Rig: <b>Precision 404</b>	Spud (est.):
BOPE Info: <b>5.0 x 13 3/8 rotating head from 600' to 4,450' 11 5M BOP stack and 5M kill lines and choke manifold used from 4,450' to 9,250' 11 10M BOE w/rotating head, 5M annular, 3.5 rams, blind rams &amp; mud cross from 9,250' to TD</b>	



**DRILLING PROGRAM**

CASING PROGRAM	SIZE	INTERVAL		WT.	GR.	CPLG.	BURST	COLLAPSE	TENSION
CONDUCTOR	13 3/8"	0	600	54.5	J-55	LTC	2,730	1,140	1,399
SURFACE	9-5/8"	0	4450	40.00	N-80	LTC	3,090	5,750	820
INTERMEDIATE	7"	0	9250	29.00	P-110	LTC	11,220	8,530	797
PRODUCTION LINER	4 1/2"	9050	12200	13.50	P-110	LTC	12,410	10,680	338

CEMENT PROGRAM		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
CONDUCTOR		600	Class G + 3% CACL2	758	100%	15.8 ppg	1.15
SURFACE	Lead	3,950	Boral Craig POZ 35%, Mountain G 65%, Bentonite Wyoming 8%, Silicate 5 lbm/sk, Pol-E Flake 0.125 lbm/sk, Kwik Seal 0.25 lb/sk	650	75%	11.0 ppg	3.16
	Tail	500	Halco-light premium+3 lb/sk Silicate+0.3% Econolite+1% Salt+0.25 lbm/sk Kol-Seal+0.24 lb/sk Kwik Seal+ HR-5	191	50%	14.2 ppg	1.33
INTERMEDIATE	Lead	4,300	Halco-Light-Premium+4% Bentonite+0.4% Econolite+0.2% Halad322+3 lb/sk Silicalite Compacted+0.8% HR-5+ 0.125 lb/sk Poly-E-Flake	306	10%	12.0 ppg	2.31
	Tail	1,000	Halco-Light-Premium+0.2% Econolite+0.3% Versaset+0.2% Halad322+0.8% HR-5+ 0.3% SuperCBL+ 0.125 lb/sk Poly-E-Flake	91	10%	12.5 ppg	1.91
PRODUCTION LINER		3,150	Halco- 50/50 Poz Premium Cement+20% SSA-1+0.3% Super CBL+ 0.3% Halad-344+0.3% Halad-413+ 0.2% SCR-100+ 0.125 lb/sk Poly-E-Flake + 3 lb/sk Silicat	232	25%	12.30	1.61

FLOAT EQUIPMENT & CENTRALIZERS	
CONDUCTOR	PDC drillable guide shoe, 1 joint, PDC drillable float collar. Thread lock all float equipment. Install bow spring centralizers on the bottom 3 joints of casing.
SURFACE	PDC drillable guide shoe, 1 joint casing, PDC drillable float collar & Stage collar. Thread lock all float equipment. Install bow spring centralizers on the bottom 3 joints of casing & every 3rd joint thereafter.
INTERMEDIATE	PDC drillable 10M,P-110 float shoe, 1 joint, PDC drillable 10M, P-110 float collar. Thread lock all float equipment. Maker joint at 8,000'.
LINER	Float shoe, 1 joint, float collar. Thread lock all FE. Maker joints every 1000'.

PROJECT ENGINEER(S): Joe Cawthorn 713-997-5929MANAGER: Tommy Gaydos

EP ENERGY E&P COMPANY, L.P.  
TAYLOR 3-9C4  
SECTION 9, T3S, R4W, U.S.B.&M.

PROCEED NORTH ON PAVED STATE HIGHWAY 87 FROM THE INTERSECTION OF HIGHWAY 87 WITH U.S. HIGHWAY 40 IN DUCHESNE, UTAH APPROXIMATELY 4.55 MILES TO AN INTERSECTION;

TURN RIGHT AND TRAVEL EAST 2.64 MILES ON A GRAVEL ROAD TO THE BEGINNING OF THE ACCESS ROAD;

TURN LEFT AND FOLLOW ROAD FLAGS NORTHERLY AND WESTERLY 0.46 MILES TO THE PROPOSED WELL LOCATION;

TOTAL DISTANCE FROM DUCHESNE, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 7.65 MILES.



**EP ENERGY E & P COMPANY, L.P.****FIGURE #2**

LOCATION LAYOUT FOR


TAYLOR 3-9C4

SECTION 9, T3S, R4W, U.S.B.&amp;M.

900' FSL, 1750' FEL

1"=40'  
X-SECTION  
SCALE  
1"=80'

NOTE: ALL CUT/FILL  
SLOPES ARE 1½:1  
UNLESS OTHERWISE  
NOTED



## APPROXIMATE YARDAGES

TOTAL CUT (INCLUDING PIT) = 10,479 CU. YDS.

PIT CUT = 4572 CU. YDS.



TOPSOIL STRIPPING: (6") = 2530 CU. YDS.

REMAINING LOCATION CUT = 3377 CU. YDS.

TOTAL FILL = 1856 CU. YDS.

LOCATION SURFACE GRAVEL=1374 CU. YDS. (4" DEEP)

ACCESS ROAD GRAVEL=640 CU. YDS.



**JERRY D. ALLRED & ASSOCIATES**  
SURVEYING CONSULTANTS

1235 NORTH 700 EAST--P.O. BOX 975  
DUCHESNE, UTAH 84021  
(435) 738-5352

13 NOV 2012

01-128-326

RECEIVED: January 08, 2013





**EP ENERGY E & P COMPANY, L.P.****FIGURE #3**

LOCATION LAYOUT FOR

TAYLOR 3-9C4

SECTION 9, T3S, R4W, U.S.B.&amp;M.

900' FSL, 1750' FEL

**JERRY D. ALLRED & ASSOCIATES**  
SURVEYING CONSULTANTS1235 NORTH 700 EAST--P.O. BOX 975  
DUCHESNE, UTAH 84021  
(435) 738-5352

13 NOV 2012

01-128-326

**RECEIVED:** January 08, 2013

FOUND FEDERAL MONUMENT  
AT QUARTER CORNER

Commencing at the Southeast Corner of Section 9, Township 3 South, Range 4 West of the United States Base and Meridian,  
 Thence North 52°52'26" West 1872.74 feet to the TRUE POINT OF BEGINNING;  
 Thence South 00°00'40" West 475.00 feet;  
 Thence North 89°59'20" West 475.00 feet;  
 Thence North 00°00'40" East 475.00 feet;  
 Thence South 89°59'20" East 475.00 feet to the TRUE POINT OF BEGINNING, containing 5.18 acres.

A 66 feet wide access road, power line, and pipeline corridor right-of-way over portions of Section 3 Township 3 South, Range 4 West of the Uintah Special Base and Meridian, the centerline of said right-of-way being further described as follows:

Commencing at the South Quarter Corner of Section 9;  
Thence North 54°59'45" East 1429.69 feet to the TRUE POINT OF BEGINNING;  
Thence South 89°55'51" East 547.48 feet;  
Thence South 00°00'07" West 766.77 feet;  
Thence South 89°21'07" West 305.34 feet;  
Thence South 41°14'44" West 44.67 feet to the North line of a proposed road. Said right-of-way being 1664.26 feet in length with the side lines being shortened or elongated to intersect said road boundary and existing road lines.

This is to certify that this plat was prepared from the field notes and electronic data collector files of an actual survey made by me, or under my personal supervision, of the use area and access road, power line, and pipeline corridor right-of-way shown hereon, and that the monuments indicated were found or set during said survey, and that this plat accurately represents said survey to the best of my knowledge.


A circular professional seal for Jerry D. Alred, a Professional Land Surveyor in the State of Utah. The seal features the text "PROFESSIONAL LAND SURVEYOR" around the top inner edge and "STATE OF UTAH" around the bottom inner edge. In the center, it reads "No. 148651", "JERRY D.", and "ALRED". A date stamp "13 NOV 12" is located on the left side. A red ink signature, "Jerry D. Alred", is written across the seal.

THE BASIS OF BEARINGS IS GEODETIC NORTH DERIVED


CORNER LOCATED AT LAI, 40°15'22.90258"N AND LONG. 110°23'21.19760"W USING THE UTAH STATE G.P.S. VIRTUAL REFERENCE STATION CONTROL NETWORK MAINTAINED AND OPERATED BY THE AUTOMATED GEOGRAPHIC REFERENCE CENTER

The logo is a circular emblem divided into four quadrants. The top-left quadrant contains a stylized human figure with arms raised. The top-right quadrant contains an equilateral triangle. The bottom-left quadrant contains a circle with a vertical line and an arrow pointing upwards. The bottom-right quadrant contains a stylized torch or flame.

LINE	BEARING	DISTANCE
L1	S 00°00'40" W	475.00'
L2	N 89°59'20" W	475.00'
L3	N 00°00'40" E	475.00'
L4	S 89°59'20" E	475.00'
L5	S 89°55'51" E	547.48'
L6	S 00°00'07" W	766.77'
L7	S 89°21'07" W	305.34'
L8	S 41°14'44" W	44.67'



SCALE: 1"=400'



EP ENERGY E&P COMPANY, L.P.  
SURFACE USE AREA  
TAYLOR 3-9C4  
5.18 ACRES

TAYLOR RANDY  
SW 1/4 SE 1/4

EAST DUCHESNE  
WATER

54°59'45"

FOUR  
AT


PROPOSED ROAD

HERNANDEZ MARCIAL  
NW¼NE¼

HERNANDEZ MARCIAL  
NE $\frac{1}{4}$ NE $\frac{1}{4}$


*N 00°26'36" E 2613.58'*

# 5M BOP STACK and CHOKE MANIFOLD SYSTEM






10000-15000-20000 psi System



RECEIVED: January 08, 2013




**LEGEND:**

◆ PROPOSED WELL LOCATION

01-128-326

**JERRY D. ALLRED & ASSOCIATES**  
SURVEYING CONSULTANTS

1235 NORTH 700 EAST--P.O. BOX 975  
DUCHESTER, UTAH 84021  
(435) 738-5352

**EP ENERGY E & P COMPANY, L.P.**

TAYLOR 3-9C4  
SECTION 9, T3S, R4W, U.S.B.&M.

900' FSL 1750' FEL


**TOPOGRAPHIC MAP "A"**

SCALE: 1"=10,000'

4 OCT 2012


**RECEIVED:** January 08, 2013



**LEGEND:**


- PROPOSED WELL LOCATION**
- PROPOSED ACCESS ROAD**
- EXISTING GRAVEL ROAD**
- EXISTING DIRT ROAD**

01-128-326



**JERRY D. ALLRED & ASSOCIATES**  
SURVEYING CONSULTANTS

1235 NORTH 700 EAST--P.O. BOX 975  
DUCHESTER, UTAH 84021  
(435) 738-5352


**EP ENERGY E & P COMPANY, L.P.**

**TAYLOR 3-9C4**  
**SECTION 9, T3S, R4W, U.S.B.&M.**  
**900' FSL 1750' FEL**

**TOPOGRAPHIC MAP "B"**

SCALE: 1"=2000'  
13 NOV 2012

**RECEIVED:** January 08, 2013

**LEGEND:**


⊕ PROPOSED WELL LOCATION

● ○ + ⊕ ⊙ ⊕ ○

01-128-326

**JERRY D. ALLRED & ASSOCIATES**  
SURVEYING CONSULTANTS

1235 NORTH 700 EAST--P.O. BOX 975  
DUCHESNE, UTAH 84021  
(435) 738-5352



**EP ENERGY E & P COMPANY, L.P.**

TAYLOR 3-9C4  
SECTION 9, T3S, R4W, U.S.B.&M.  
900' FSL 1750' FEL

**TOPOGRAPHIC MAP "C"**

SCALE: 1"=2000'  
13 NOV 2012

**RECEIVED:** January 08, 2013



**AFFIDAVIT OF SURFACE DAMAGE AND RIGHT-OF-WAY AGREEMENTS**

Michael J. Walcher personally appeared before me, and, being duly sworn, deposes and says:

1. My name is Michael J. Walcher. I am a Sr. Staff Landman for EP Energy E&P Company, L.P., whose address is 1001 Louisiana St., Houston, Texas 77002 ("EP Energy").
2. EP Energy is the operator of the proposed Taylor 3-9C4 well (the "Well") to be located in the SW/4 SE/4 of Section 9, Township 3 South, Range 4 West, USM, Duchesne County, Utah (the "Drillsite Location"). The surface owner of the Drillsite Location is Randy J. Taylor and Sadie M. Taylor, husband and wife, as joint tenants, whose address is P. O. Box 941, Duchesne, Utah 84021 (the "Surface Owner"). The Surface Owner's telephone number is (435) 823-5502.
3. EP Energy and the Surface Owner have entered into a Damage Settlement and Release Agreement dated January 2, 2013 to cover any and all injuries or damages of every character and description sustained by the Surface Owner or Surface Owner's property as a result of operations associated with the drilling of the Well.
4. EP Energy and the Surface Owner have also entered into a Right-Of-Way Agreement dated January 2, 2013, for an access road and pipeline corridor across the SE/4 SE/4 and the NE/4 SW/4 SE/4 of Section 9, Township 3 South, Range 4 West, USM, Duchesne County, Utah.

FURTHER AFFIANT SAYETH NOT.

Michael J. Walcher

**ACKNOWLEDGMENT**

STATE OF TEXAS                   §  
   §  
CITY AND COUNTY OF HARRIS   §

Before me, a Notary Public, in and for this state, on this 3rd day of January, 2013, personally appeared Michael J. Walcher, to me known to be the identical person who executed the within and foregoing instrument, and acknowledged to me that he executed the same as his own free and voluntary act and deed for the uses and purposes therein set forth.

  
\_\_\_\_\_  
NOTARY PUBLIC

My Commission Expires:



EP Energy E&P Company, L.P.

**Related Surface Information**

1. **Current Surface Use:**

- Livestock Grazing and Oil and Gas Production.

2. **Proposed Surface Disturbance:**

- The road will be crown and ditch. Water wings will be constructed on the access road as needed.
- The topsoil will be windrowed and re-spread in the borrow area.
- New road to be constructed will be approximately .46 miles in length and 66 feet wide.
- All equipment and vehicles will be confined to the access road, pad and area specified in the APD.

3. **Location Of Existing Wells:**

- Existing oil, gas wells within one (1) mile radius of proposed well are provided in EXHIBIT C.

4. **Location And Type Of Drilling Water Supply:**

- Drilling water: Duchesne City Water

5. **Existing/Proposed Facilities For Productive Well:**

- There are no existing facilities that will be utilized for this well.
- A pipeline corridor .46 miles will parallel the proposed access road. The corridor will contain one 4 inch gas line and one 2 inch gas line and one 2 inch Salt Water disposal line. Rehabilitation of unneeded, previously disturbed areas will consist of backfilling and contouring the reserve pit area; backsloping and contouring all cut and fill slopes. These areas will be reseeded. Refer to plans for reclamation of surface for details.
- Upgrade and maintain access roads and drainage control structures (e.g., culverts, drainage dips, ditching, etc.) as necessary to prevent soil erosion and accommodate safe, year-round traffic.

6. **Construction Materials:**

- Native soil from road and location will be used for construction materials along with gravel and/or scoria road base material. In the event that conditions should necessitate graveling of all or part of the access road and location, surfacing materials will be purchased from commercial suppliers in the marketing area.

7. **Methods For Handling Waste Disposal:**

- The reserve pit will be designed to prevent the collection of surface runoff and will be constructed with a minimum of ½ the total depth below the original ground surface on the lowest point with the pit. The pit will be lined with a 20-mil polyethylene to prevent leakage of fluids. The liner will be rolled into place and secured at the ends, i.e. buried on top of the pit berms. Prior to use, the reserve pit will be fenced on three sides; the fourth side will be fenced at the time the rig is removed. Drilling fluids, cuttings and produced water will be contained in the reserve pit (trash will be placed in the trash cage). Fluids in the reserve pit will be allowed to evaporate prior to pit burial.
- Garbage and other trash will be contained in the portable trash cage and hauled off the location to an authorized disposal site. Any trash on the pad will be cleaned up prior to the rig moving off location and hauled to an authorized disposal site.
- Sewage will be handled in Portable Toilets.
- Produced water will be placed in the reserve pit for a period not to exceed ninety days after initial production. Any hydrocarbons produced during completion work will be contained in test tanks and removed from the location at a later date.
- Water from the reserve pit may be used for drilling of additional wells. The water will be trucked along access roads as approved in pertinent APD's

8. **Ancillary Facilities:**

- There will be no ancillary facilities associated with this project.

9. **Surface Reclamation Plans:**

Backfilling of the pits will be done when dry. In the event of a dry hole, the location will be re-contoured, the topsoil will be distributed evenly over the entire location, and the seedbed prepared.

- Seed will be planted after September 15<sup>th</sup>, and prior to ground frost, or seed will be planted after the frost has left and before May 15<sup>th</sup>. Slopes to steep for machinery will be hand broadcast and raked with twice the specified amount of seed.
  1. The construction program and design are on the attached cut, fill and cross sectional diagrams.
  2. Prior to construction, all topsoil will be removed from the entire site and stockpiled. Topsoil for this site is the first 6 inches of soil materials.
  3. After the location has been reshaped and after redistributing the topsoil, the operator will rip and scarify the drilling platform and access road on the contour, to a depth of at least 12 inches.
- Rehabilitation will begin upon the completion of the drilling. Complete rehabilitation will depend on weather conditions and the amount of time required to dry the reserve pit.
  1. All rehabilitation work including seeding will be completed as soon as weather and the reserve pit conditions are appropriate.
  2. Landowner will be contacted for rehabilitation requirements.

10. **Surface Ownership:**

Randy J. and Sadie M. Taylor  
P.O. Box 941  
Duchesne, Utah 84021  
435-823-5502

**Other Information:**

- The surface soil consists of clay, and silt.
- Flora – vegetation consists of the following: Sagebrush, Juniper and prairie grasses.
- Fauna – antelope, deer, coyotes, raptors, small mammals, and domestic grazing animals.
- Current surface uses – Livestock grazing and mineral exploration and production.

• **Operator and Contact Persons:**

**Construction and Reclamation:**

EP Energy E&P Company, L.P.  
Wayne Garner  
PO Box 410  
Altamont, Utah 84001  
435-454-3394 – Office  
435-823-1490 – Cell


**Regarding This APD**

EP Energy E&P Company, L.P.  
Maria S. Gomez  
1001 Louisiana, Rm 2730D  
Houston, Texas 77002  
713-997-5038 – Office

**Drilling**



EP Energy E&P Company, L.P.  
Joe Cawthorn – Drilling Engineer  
1001 Louisiana, Rm 2523B  
Houston, Texas 77002  
713-997-5929 – office  
832-465-2882 – Cell





**API Number: 4301351954**  
**Well Name: Taylor 3-9C4**  
**Township T03.0S Range R04.0W Section 09**  
**Meridian: UBM**  
 Operator: EP ENERGY E&P COMPANY, L.P.  
 Map Prepared:  
 Map Produced by Diana Mason

Units	Wells Query
<b>STATUS</b>	<b>Status</b>
ACTIVE	APD - Approved Permit
EXPLORATORY	DRIL - Spudded (Drilling Commenced)
GAS STORAGE	GIW - Gas Injection
NF PP OIL	GS - Gas Storage
NF SECONDARY	LOC - New Location
PI OIL	OPS - Operation Suspended
PP GAS	PA - Plugged Abandoned
PP GEOTHERM	PGW - Producing Gas Well
PP OIL	POW - Producing Oil Well
SECONDARY	SGW - Shut-in Gas Well
TERMINATED	SOW - Shut-in Oil Well
<b>Fields</b>	TA - Temp. Abandoned
Unknown	TW - Test Well
ABANDONED	WDW - Water Disposal
ACTIVE	WW - Water Injection Well
COMBINED	WSW - Water Supply Well
INACTIVE	Bottom Hole Location - Oil/Gas/Dib
STORAGE	
TERMINATED	



Well Name	EP ENERGY E&P COMPANY, L.P. Taylor 3-9C4 43013519540000			
String	COND	SURF	I1	L1
Casing Size(in)	13.375	9.625	7.000	4.500
Setting Depth (TVD)	600	4450	9250	12200
Previous Shoe Setting Depth (TVD)	0	600	4450	9250
Max Mud Weight (ppg)	8.8	9.5	10.5	12.0
BOPE Proposed (psi)	1000	5000	5000	10000
Casing Internal Yield (psi)	2730	5750	11220	12410
Operators Max Anticipated Pressure (psi)	7613			12.0

Calculations	COND String	13.375	"
Max BHP (psi)	.052*Setting Depth*MW=	275	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	203	YES rotating head
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	143	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	143	NO OK
Required Casing/BOPE Test Pressure=		600	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient


Calculations	SURF String	9.625	"
Max BHP (psi)	.052*Setting Depth*MW=	2198	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	1664	YES rotating head + 5M annular
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	1219	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	1351	NO OK
Required Casing/BOPE Test Pressure=		4025	psi
*Max Pressure Allowed @ Previous Casing Shoe=		600	psi *Assumes 1psi/ft frac gradient

Calculations	I1 String	7.000	"
Max BHP (psi)	.052*Setting Depth*MW=	5051	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	3941	YES A 5M BOP stack, 5M Annular, and 5M kill lines &
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	3016	YES choke manifold
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	3995	YES OK
Required Casing/BOPE Test Pressure=		7854	psi
*Max Pressure Allowed @ Previous Casing Shoe=		4450	psi *Assumes 1psi/ft frac gradient

Calculations	L1 String	4.500	"
Max BHP (psi)	.052*Setting Depth*MW=	7613	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	6149	YES 10M BOE w/rotating head, 5M annular, blind rams &
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	4929	YES mud cross
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	6964	YES OK
Required Casing/BOPE Test Pressure=		8687	psi
*Max Pressure Allowed @ Previous Casing Shoe=		9250	psi *Assumes 1psi/ft frac gradient

## 43013519540000 Taylor 3-9C4

## Casing Schematic



Well name:	<b>43013519540000 Taylor 3-9C4</b>	
Operator:	<b>EP ENERGY E&amp;P COMPANY, L.P.</b>	
String type:	Conductor	Project ID: 43-013-51954
Location:	DUCHESNE COUNTY	

**Design parameters:****Collapse**

Mud weight: 8.800 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 82 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: 177 ft

**Burst**

Max anticipated surface pressure: 202 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 274 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

**Non-directional string.**

Tension is based on air weight.  
Neutral point: 522 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	600	13.375	54.50	J-55	ST&C	600	600	12.49	7445
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	274	1130	4.120	274	2730	9.95	32.7	514	15.72 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: February 6, 2013  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 600 ft, a mud weight of 8.8 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	<b>43013519540000 Taylor 3-9C4</b>	
Operator:	<b>EP ENERGY E&amp;P COMPANY, L.P.</b>	
String type:	Surface	Project ID: 43-013-51954
Location:	DUCHESNE COUNTY	

**Design parameters:****Collapse**

Mud weight: 9.500 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 136 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 100 ft

Cement top: Surface

**Burst**

Max anticipated surface pressure: 3,010 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 3,989 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.70 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on air weight.  
Neutral point: 3,821 ft

**Non-directional string.****Re subsequent strings:**

Next setting depth: 9,250 ft  
Next mud weight: 10.500 ppg  
Next setting BHP: 5,045 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 4,450 ft  
Injection pressure: 4,450 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	4450	9.625	40.00	N-80	LT&C	4450	4450	8.75	56625

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	2196	3090	1.407	3989	5750	1.44	178	737	4.14 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: February 6, 2013  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 4450 ft, a mud weight of 9.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	<b>43013519540000 Taylor 3-9C4</b>	
Operator:	<b>EP ENERGY E&amp;P COMPANY, L.P.</b>	
String type:	Intermediate	Project ID: 43-013-51954
Location:	DUCHESNE COUNTY	

**Design parameters:****Collapse**

Mud weight: 10.500 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 204 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: 5,817 ft

**Burst**

Max anticipated surface pressure: 4,921 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 6,956 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

Tension is based on air weight.  
Neutral point: 7,780 ft

**Non-directional string.****Re subsequent strings:**

Next setting depth: 12,200 ft  
Next mud weight: 12.000 ppg  
Next setting BHP: 7,605 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 9,250 ft  
Injection pressure: 9,250 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	9250	7	29.00	P-110	LT&C	9250	9250	6.059	104457
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	5045	8530	1.691	6956	11220	1.61	268.3	797	2.97 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: February 6, 2013  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 9250 ft, a mud weight of 10.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	<b>43013519540000 Taylor 3-9C4</b>	
Operator:	<b>EP ENERGY E&amp;P COMPANY, L.P.</b>	
String type:	Production Liner	Project ID: 43-013-51954
Location:	DUCHESNE COUNTY	

**Design parameters:****Collapse**

Mud weight: 12.000 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 245 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

**Burst:**

Design factor 1.00

Cement top: 9,646 ft

**Burst**

Max anticipated surface pressure: 4,921 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 7,605 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

Liner top: 9,050 ft

**Non-directional string.**

Tension is based on air weight.  
Neutral point: 11,633 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	3200	4.5	13.50	P-110	LT&C	12200	12200	3.795	17931
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	7605	10680	1.404	7605	12410	1.63	43.2	338	7.82 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: February 6, 2013  
Salt Lake City, Utah

**Remarks:**

For this liner string, the top is rounded to the nearest 100 ft. Collapse is based on a vertical depth of 12200 ft, a mud weight of 12 ppg. The Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

**Operator** EP ENERGY E&P COMPANY, L.P.  
**Well Name** Taylor 3-9C4  
**API Number** 43013519540000      **APD No** 7456    **Field/Unit** ALTAMONT  
**Location: 1/4,1/4 SWSE Sec 9 Tw 3.0S Rng 4.0W 900 FSL 1750 FEL**  
**GPS Coord (UTM)** 556302 4453528      **Surface Owner** Randy J. and Sadie M. Taylor

### **Participants**

Randy Taylor (Landowner); Jared Thacker (EP Energy); David Allred (EP Energy, land); Ryan Allred & Clayton Packer (Allred & Associates); Dennis Ingram (Division Oil, Gas & Mining)

### **Regional/Local Setting & Topography**

The proposed Taylor 3-9C4 well site is located in northeastern Utah approximately 4.55 miles north of Duchesne along highway 87, then easterly along an existing county road for 2.64 miles, then north along the proposed access road into well pad. The surface is relatively flat but slopes slightly to the southeast. The surface topography changes little across Blue Bench, which is mostly flat, open rangeland that was once irrigated to grow alfalfa. The surface does change approximately 4.0 miles to the west where this bench habitat drops off into the Duchesne River Drainage; the topography also slopes gently in a southerly direction until it reaches the Duchesne River Drainage some two plus miles away. To the north, broken sandstone shelves are common as the elevation rises into pinion juniper habitat.

### **Surface Use Plan**

**Current Surface Use**  
Grazing

<b>New Road Miles</b>	<b>Well Pad</b>	<b>Src Const Material</b>	<b>Surface Formation</b>
0.46	<b>Width 342 Length 425</b>	Onsite	UNTA

**Ancillary Facilities** Y

### **Waste Management Plan Adequate?**

### **Environmental Parameters**

**Affected Floodplains and/or Wetlands** N

#### **Flora / Fauna**

Rabbit brush and weeds; vegetation not suitable for wildlife, potential rabbit, coyote, mule deer, fox and birds of prey.

#### **Soil Type and Characteristics**

Snow covered, Reddish in color, fine grained sandy loam, silt.

**Erosion Issues** N

**Sedimentation Issues** N

**Site Stability Issues** N



**Drainage Diversion Required? N****Berm Required? Y****Erosion Sedimentation Control Required? N****Paleo Survey Run? N    Paleo Potential Observed? N    Cultural Survey Run? N    Cultural Resources? N****Reserve Pit**

<b>Site-Specific Factors</b>		<b>Site Ranking</b>
<b>Distance to Groundwater (feet)</b>	>200	0
<b>Distance to Surface Water (feet)</b>	>1000	0
<b>Dist. Nearest Municipal Well (ft)</b>	>5280	0
<b>Distance to Other Wells (feet)</b>	>1320	0
<b>Native Soil Type</b>	High permeability	20
<b>Fluid Type</b>	Fresh Water	5
<b>Drill Cuttings</b>	Normal Rock	0
<b>Annual Precipitation (inches)</b>		0
<b>Affected Populations</b>		
<b>Presence Nearby Utility Conduits</b>	Not Present	0
	<b>Final Score</b>	25    1 Sensitivity Level

**Characteristics / Requirements**

Proposed reserve pit in cut on the northern side of location, measuring 110' wide by 150' long by 12 feet deep, and having prevailing winds from the west.

**Closed Loop Mud Required?    Liner Required? Y    Liner Thickness 16    Pit Underlayment Required?****Other Observations / Comments**

Landowner agreement in place, no issues, landowners wants two cattle guards and net wire fencing along road and location because of grazing, snow covered surface.

Dennis Ingram  
Evaluator

1/10/2013  
Date / Time

# Application for Permit to Drill

## Statement of Basis

### Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
7456	43013519540000	LOCKED	OW	P	No
Operator	EP ENERGY E&P COMPANY, L.P.		Surface Owner-APD	Randy J. and Sadie M. Taylor	
Well Name	Taylor 3-9C4		Unit		
Field	ALTAMONT		Type of Work	DRILL	
Location	SWSE 9 3S 4W U 900 FSL 1750 FEL GPS Coord (UTM) 556302E 4453528N				

#### Geologic Statement of Basis

El Paso proposes to set 600 feet of conductor and 4,450 feet of surface casing both of which will be cemented to surface. The surface and intermediate holes will be drilled utilizing fresh water mud. The estimated depth to the base of moderately saline ground water is 1,750 feet. A search of Division of Water Rights records indicates that there are 5 water wells within a 10,000 foot radius of the center of Section 9. Wells range between 285 and 500 feet in depth and are used for irrigation, stock watering, domestic and oilfield purposes. These wells probably produce from the Duchesne River Formation. The Duchesne River Formation is made up of sandstones with interbedded shales and is the most prominent fresh water aquifer in the area. The proposed casing and cement program should adequately protect ground water in this area.

Brad Hill  
APD Evaluator

1/17/2013  
Date / Time

#### Surface Statement of Basis

A presite visit was scheduled and done on January 10, 2013 to take input and address issues regarding the construction and drilling of the Taylor 3-9C4 well. Randy J. and Sadie M. Taylor were shown as the landowner of record and therefore invited to the presite meeting prior to the visit and attended presite.

The immediate surface area is rangeland with sagebrush with sagebrush type habitat, some housing and trailer houses further to the west. The surfaced slopes gently to the east and does not have any drainages issues. The reserve pit shall be constructed immediately off the north side of the location. The operator shall install a 20 mil synthetic liner in the pit as stipulation on the operations plan to prevent seepage in this sandy soil. The reserve pit shall be wire net fenced with two cattle guards installed to prevent cattle from entering location. Snow covered surface during time of presite.

Dennis Ingram  
Onsite Evaluator

1/10/2013  
Date / Time

#### Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 20 mils shall be properly installed and maintained in the reserve pit.
Pits	The reserve pit should be located on the north side of the location.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.

API Well Number: 43013519540000

Surface

The reserve pit shall be fenced upon completion of drilling operations.

**CONFIDENTIAL**

**RECEIVED:** February 19, 2013

## WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 1/8/2013

API NO. ASSIGNED: 43013519540000

WELL NAME: Taylor 3-9C4

OPERATOR: EP ENERGY E&amp;P COMPANY, L.P. (N3850)

PHONE NUMBER: 713 997-5038

CONTACT: Maria S. Gomez

PROPOSED LOCATION: SWSE 09 030S 040W

Permit Tech Review: ☒

SURFACE: 0900 FSL 1750 FEL

Engineering Review: ☒

BOTTOM: 0900 FSL 1750 FEL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.23029

LONGITUDE: -110.33818

UTM SURF EASTINGS: 556302.00

NORTHINGS: 4453528.00

FIELD NAME: ALTAMONT

LEASE TYPE: 4 - Fee

LEASE NUMBER: Fee

PROPOSED PRODUCING FORMATION(S): GREEN RIVER-WASATCH

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

## RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: STATE - 400JU0708☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: Duchesne City☐ RDCC Review:☒ Fee Surface Agreement☐ Intent to Commingle

Commingling Approved

## LOCATION AND SITING:

☐ R649-2-3.

Unit:

☐ R649-3-2. General☐ R649-3-3. Exception☒ Drilling Unit

Board Cause No: Cause 139-90

Effective Date: 5/9/2012

Siting: 4 Prod LGRRV-WSTC Wells

☐ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 5 - Statement of Basis - bhll  
8 - Cement to Surface -- 2 strings - hmadonald  
13 - Cement Volume Formation (3a) - hmadonald

RECEIVED: February 19, 2013



GARY R. HERBERT  
Governor

GREGORY S. BELL  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

## Permit To Drill

\*\*\*\*\*

**Well Name:** Taylor 3-9C4  
**API Well Number:** 43013519540000  
**Lease Number:** Fee  
**Surface Owner:** FEE (PRIVATE)  
**Approval Date:** 2/19/2013

### Issued to:

EP ENERGY E&P COMPANY, L.P., 1001 Louisiana, Houston, TX 77002

### Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 139-90. The expected producing formation or pool is the GREEN RIVER-WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

### Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

### Conditions of Approval:

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volumes for the 13 3/8" and 9 5/8" casing strings shall be determined from actual hole diameters in order to place cement from the pipe setting depths back to the surface.

Cement volume for the 7" intermediate string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to 3950' MD as stated in drill plan and in order to adequately isolate the Green River formation.

### Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

### **Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels  
OR  
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website  
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program  
- contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

### **Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office  
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office  
801-231-8956 - after office hours

### **Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

**Approved By:**

A handwritten signature in black ink, appearing to read "J. Rogers", written over a faint horizontal line.

For John Rogers  
Associate Director, Oil & Gas

3/5/13

Spud 24hr Notification spud TAYLOR 3-9C4 - caroldaniels@utah.gov - State of Utah Mail

Search Images Mail Drive Calendar Sites Groups Contacts Mobile More ▾



S-09 +035 R04W

caroldaniels@utah.gov

Mail

More

1 of 140

COMPOSE

Well: . TAYLOR 3-9C4  
API# 43013519540000

People (9)

CONFIDENTIAL

RLANDRIG008

rlandrig008@epenergy.com

Show details

Inbox (18)

Starred

Important

Sent Mail

Drafts (1)

Cabinet

Follow up

Misc

Notes

Best Regards

Tony Wilkerson  
EP Energy  
Rig Site Supervisor  
Altamont, Utah  
C: 435-828-1725

Search people...



Click here to [Reply](#), [Reply to all](#), or [Forward](#)

alexishuefner

Don Staley

Diana Mason

barbara\_nicol

Brady Riley Inv...

Cordell Wold

Dustin Doucet

Rig - SST 54 (...)

RLANDRIG008

0% full

Using 0.1 GB of your 25 GB

©2013 Google - [Terms of Service](#) -  
[Privacy Policy](#) - [Program Policies](#)

Powered by **Google**

Last account activity: 30 minutes ago  
[Details](#)

RECEIVED

MAR 05 2013

DIV. OF OIL, GAS & MINING



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator: EP Energy E&P Company, L.P. Operator Account Number: N 3850  
Address: 1001 Louisiana, Room 2730D  
city Houston  
state TX zip 77002 Phone Number: (713) 997-5038

**Well 1**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4301351954	Taylor 3-9C4		SWSE	9	3S	4W	Duchesne
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	new	18956	3/4/2013			3/13/2013	
Comments: Spud Notification WS-GR <div style="text-align: right; font-weight: bold; font-size: 1.2em;">CONFIDENTIAL</div>							

**Well 2**

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

**Well 3**

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

RECEIVED

MAR 11 2013

Div. of Oil, Gas & Mining

Maria S. Gomez

Name (Please Print)

*Maria S. Gomez*

Signature

Principle Regulatory Analyst

Title

3/5/2013

Date

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: Taylor 3-9C4	
2. NAME OF OPERATOR: EP ENERGY E&P COMPANY, L.P.	9. API NUMBER: 43013519540000	
3. ADDRESS OF OPERATOR: 1001 Louisiana, Houston, TX, 77002	PHONE NUMBER: 713 997-5038 Ext	9. FIELD and POOL or WILDCAT: ALTAMONT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0900 FSL 1750 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSE Section: 09 Township: 03.0S Range: 04.0W Meridian: U		COUNTY: DUCHESNE
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <b>3/20/2013</b>  <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:  <input type="checkbox"/> SPUD REPORT Date of Spud:  <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE  <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION  OTHER: <input type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Change surface casing (9 5/8") setting depth from 4450' to 3600' and production liner from 4.5" 13.5# P-110 to 5" 18# HCP-110 STL.

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: March 28, 2013


By: *Derek Duff*

NAME (PLEASE PRINT) Maria S. Gomez	PHONE NUMBER 713 997-5038	TITLE Principal Regulatory Analyst
SIGNATURE N/A		DATE 3/19/2013



## Drilling Schematic

<b>Company Name:</b> EP ENERGY	<b>Date:</b> January 3, 2012
<b>Well Name:</b> Taylor 3-9C4	<b>TD:</b> 11,700
<b>Field, County, State:</b> Altamont - Bluebell, Duchesne, Utah	<b>AFE #:</b>
<b>Surface Location:</b> Sec 9 T3S R4W 900' FSL 1750' FEL	<b>BHL:</b> Straight Hole
<b>Objective Zone(s):</b> Green River, Wasatch	<b>Elevation:</b> 5999
<b>Rig:</b> Precision 404	<b>Spud (est.):</b>
<b>BOPE Info:</b> 5.0 x 13 3/8 rotating head from 600' to 3,600' 11 5M BOP stack and 5M kill lines and choke manifold used from 3,600' to 9,250' 11 10M BOE w/rotating head, 5M annular, 3.5 rams, blind rams & mud cross from 9,250' to TD	



**DRILLING PROGRAM**

CASING PROGRAM	SIZE	INTERVAL		WT.	GR.	CPLG.	BURST	COLLAPSE	TENSION
CONDUCTOR	13 3/8"	0	600	54.5	J-55	LTC	2,730	1,140	1,399
SURFACE	9-5/8"	0	3600	40.00	N-80	LTC	3,090	5,750	820
INTERMEDIATE	7"	0	9250	29.00	P-110	LTC	11,220	8,530	797
PRODUCTION LINER	5"	9150	11700	18.00	HCP-110	STL	13,940	13,470	580

CEMENT PROGRAM		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
CONDUCTOR		600	Class G + 3% CACL2	758	100%	15.8 ppg	1.15
SURFACE	Lead	3,100	Boral Craig POZ 35%, Mountain G 65%, Bentonite Wyoming 8%, Silicate 5 lbm/sk, Pol-E Flake 0.125 lbm/sk, Kwik Seal 0.25 lb/sk	503	75%	11.0 ppg	3.16
	Tail	500	Halco-light premium+3 lb/sk Silicate+0.3% Econolite+1% Salt+0.25 lbm/sk Kol-Seal+0.24 lb/sk Kwik Seal+ HR-5	191	50%	14.2 ppg	1.33
INTERMEDIATE	Lead	5,150	Halco-Light-Premium+4% Bentonite+0.4% Econolite+0.2% Halad322+3 lb/sk Silicalite Compacted+0.8% HR-5+ 0.125 lb/sk Poly-E-Flake	367	10%	12.0 ppg	2.31
	Tail	1,000	Halco-Light-Premium+0.2% Econolite+0.3% Versaset+0.2% Halad322+0.8% HR-5+ 0.3% SuperCBL+ 0.125 lb/sk Poly-E-Flake	91	10%	12.5 ppg	1.91
PRODUCTION LINER		2,650	Halco- 50/50 Poz Premium Cement+20% SSA-1+0.3% Super CBL+ 0.3% Halad-344+0.3% Halad-413+ 0.2% SCR-100+ 0.125 lb/sk Poly-E-Flake + 3 lb/sk Silicat	144	25%	14.20	1.61

FLOAT EQUIPMENT & CENTRALIZERS	
CONDUCTOR	PDC drillable guide shoe, 1 joint, PDC drillable float collar. Thread lock all float equipment. Install bow spring centralizers on the bottom 3 joints of casing.
SURFACE	PDC drillable guide shoe, 1 joint casing, PDC drillable float collar & Stage collar. Thread lock all float equipment. Install bow spring centralizers on the bottom 3 joints of casing & every 3rd joint thereafter.
INTERMEDIATE	PDC drillable 10M,P-110 float shoe, 1 joint, PDC drillable 10M, P-110 float collar. Thread lock all float equipment. Maker joint at 8,000'.
LINER	Float shoe, 1 joint, float collar. Thread lock all FE. Maker joints every 1000'.

PROJECT ENGINEER(S): Joe Cawthorn 713-997-5929MANAGER: Tommy Gaydos

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> Fee
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> EP ENERGY E&P COMPANY, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1001 Louisiana , Houston, TX, 77002		<b>8. WELL NAME and NUMBER:</b> Taylor 3-9C4
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0900 FSL 1750 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWSE Section: 09 Township: 03.0S Range: 04.0W Meridian: U		<b>9. API NUMBER:</b> 43013519540000
<b>PHONE NUMBER:</b> 713 997-5038 Ext		<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 4/5/2013	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  

Well currently in drilling phase.

Accepted by the  
 Utah Division of  
 Oil, Gas and Mining  
**FOR RECORD ONLY**  
 April 18, 2013

<b>NAME (PLEASE PRINT)</b> Maria S. Gomez	<b>PHONE NUMBER</b> 713 997-5038	<b>TITLE</b> Principal Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 4/5/2013	

## 1 General

### 1.1 Customer Information

Company	CENTRAL DIVISION
Representative	
Address	

### 1.2 Well Information

Well	TAYLOR 3-9C4		
Project	ALTAMONT FIELD	Site	TAYLOR 3-9C4
Rig Name/No.	PRECISION DRILLING/406	Event	DRILLING LAND
Start Date	3/15/2013	End Date	
Spud Date/Time	3/18/2013	UWI	TAYLOR 3-9C4
Active Datum	KB @6,016.1ft (above Mean Sea Level)		
Afe No./Description	159844/47989 / TAYLOR 3-9C4		

## 2 Summary

### 2.1 Operation Summary

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD From (ft)	Operation
3/15/2013	6:00 19:00	13.00	MIRU	01		P	600.0	MIRU. 90% MOVED. 25% RIGGED UP.
	19:00 6:00	11.00	MIRU	01		P	600.0	SDFN.
3/16/2013	6:00 19:00	13.00	MIRU	01		P	600.0	MIRU.
	19:00 6:00	11.00	MIRU	01		P	600.0	RIGGED UP.
3/17/2013	6:00 2:00	20.00	MIRU	01		P	600.0	FINISHED RIG UP. RIG ON DAYRATE 0200HRS, 3/17/2013.
	2:00 6:00	4.00	DRLSURF	19		P	600.0	PJSM. NU & TEST DIVERter SYSTEM.
3/18/2013	6:00 9:00	3.00	DRLSURF	30		P	600.0	FINISHED DIVERter SYSTEM & FLOOR VALVES TESTING 250 / 3,000 PSI.
	9:00 20:00	11.00	DRLSURF	30		P	600.0	NU ROT HEAD. ATTEMPTED FLOWLINE RU...MISALIGNED. WELDER MODIFIED FLOWLINE. RU MGS & FLARE LINES.DRESSED SHAKERS. MIXED SPUD MUD.
	20:00 0:00	4.00	DRLSURF	14		P	600.0	PUMU RYAN'S STEERABLE ASSY. PUMU DCS & HWDP. TAGGED AT 560'.
	0:00 1:00	1.00	DRLSURF	17		P	600.0	CUT DRILL LINE. SERVICED RIG & TDU.
	1:00 2:00	1.00	DRLSURF	31		P	600.0	SUCCESSFULLY TESTED CASING TO 1,000 PSI FOR >30 MINUTES. INSERTED RH RUBBER.
	2:00 4:30	2.50	DRLSURF	72		P	600.0	DRILLED CEMENT, FLOAT EQUIPMENT, AND SHOE AT 600'
	4:30 6:00	1.50	DRLSURF	08		P	600.0	SPUDDED 0430 HRS, 03/18/2013. DRILLED 600 - 700'.
3/19/2013	6:00 8:00	2.00	DRLSURF	11		P	700.0	C & C MUD. VAUGHN RAN GYRO SURVEY.
	8:00 11:30	3.50	DRLSURF	08		P	700.0	DRILLED, 700'-860'.
	11:30 12:30	1.00	DRLSURF	42		P	860.0	MU BIT, DEEPENED MOUSEHOLE 12'.
	12:30 15:00	2.50	DRLSURF	08		P	860.0	DRILLED 860'-1,109'.
	15:00 15:30	0.50	DRLSURF	12		P	1,109.0	SERVICED RIG, TDU.
	15:30 1:30	10.00	DRLSURF	08		P	1,109.0	DRILLED 1,109'-2,149'
	1:30 2:30	1.00	DRLSURF	12		P	2,149.0	REPAIRED PUMPS.
	2:30 6:00	3.50	DRLSURF	08	DRILL ED, D	P	2,149.0	DRILLED 2,149-2,430'.
3/20/2013	6:00 15:00	9.00	DRLSURF	08		P	2,430.0	DRILLED 2430'-3060'.
	15:00 15:30	0.50	DRLSURF	12		P	3,060.0	SERVICED RIG & TDU.
	15:30 0:30	9.00	DRLSURF	08		P	3,060.0	DRILLED 3060'-3646' SCP.
	0:30 1:00	0.50	DRLSURF	15		P	3,646.0	C & C MUD.
	1:00 6:00	5.00	DRLSURF	16		P	3,646.0	BACKREAMED OUT.
3/21/2013	6:00 7:30	1.50	DRLSURF	16		P	3,646.0	FINISHED BACKREAM TO SHOE.

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duratio n (hr)	Phase	Activit y	Sub	OP Code	MD From (ft)	Operation
	7:30 8:00	0.50	DRLSURF	12		P	3,646.0	SERVICED RIG & TDU.
	8:00 9:30	1.50	DRLSURF	43		N	3,646.0	REPAIRED TDU HYDRAULIC OIL LEAK.
	9:30 13:30	4.00	DRLSURF	13		P	3,646.0	TIH/REAMED TO 3646'.
	13:30 15:30	2.00	DRLSURF	15		P	3,646.0	PUMPED SWEEP. C & C MUD.
	15:30 19:00	3.50	DRLSURF	13		P	3,646.0	TOOH TO DCs.
	19:00 23:30	4.50	DRLSURF	13		P	3,646.0	LAID DOWN DRILL COLLARS & RYAN BHA.
	23:30 0:00	0.50	DRLSURF	12		P	3,646.0	CLEARED FLOOR AND CATWALK.
	0:00 2:00	2.00	CASSURF	24		P	3,646.0	PJSM. RIGGED UP CASING TOOLS.
3/22/2013	2:00 6:00	4.00	CASSURF	24		P	3,646.0	PUMU FS & FC. RUN 9 5/8", 40#, N-80, LTC, SURFACE CASING.
	6:00 9:00	3.00	CASSURF	24		P	3,646.0	FINISHED RUN 9 5/8", 40#, N-80, LTC, SURFACE CASING. UTILIZED 26 STANDARD BOWSPRING CENTRALIZERS. CEMENT BASKET AT 400'. WASHED 15' OF FILL.
	9:00 11:30	2.50	CASSURF	24		P	3,646.0	RU HALLIBURTON HEAD. HELD PJSM WITH CEMENTERS.
	11:30 14:30	3.00	CASSURF	25		P	3,646.0	TESTED P & L TO 3,700 PSI. PUMPED 100 BBLS FW SPACER. M & P 302 BBLS / 535 SKS LEAD SLURRY AT 3.17 YIELD & 11.0 PPG. M & P 45 BBLS / 195 SKS TAIL SLURRY AT 1.30 YIELD & 14.3 PPG. RELEASED PLUG. DISPLACED WITH 252 BBLS 9.6 PPG WBM PLUS 20 BBLS FW. PLUG DOWN @ 1425 HRS, 03/21/2013 WITH 1,000 PSI. FLOWED BACK 1 BBL, FLOATS HELD. 100% RETURNS. RECOVERED 80 BBLS OF CEMENT BACK TO SURFACE. SHOE AT 3,640'.
	14:30 23:00	8.50	CASSURF	25		P	3,646.0	RD HES' HEAD. SWAPPED BAILS & ELEVATORS. PUMU X-O SUB TO DP. RAN 200' OF 1" TUBING FOR TOP JOB. TOPPED OUT WITH 21 BBLS OF 100 SKS AT 1.17 YIELD & 15.8 CLASS G CEMENT PLUS 2% CACL2. RD HALLIBURTON.
	23:00 3:00	4.00	CASSURF	29		P	3,646.0	ND DIVERTER.
	3:00 6:00	3.00	CASSURF	30		P	3,646.0	CUT OFF 13 5/8" 3M WELL HEAD & 9 5/8" CASING STUB. WELD & TEST 11" 5M WELL HEAD.
3/23/2013	6:00 15:00	9.00	CASSURF	28		P	3,646.0	NU 11" 10M B-SECTION & BOPE.
	15:00 23:30	8.50	CASSURF	30		P	3,646.0	TESTED 11" 10M BOPE. TESTED CHOKE MANIFOLD 300 / 10,000 PSI. TESTED ACCUMULATOR. TESTED UPPER AND LOWER PIPE RAMS, KILL LINE VALVES, CHOKE VALVES, TOP DRIVE LOWER VALVE, ALL 300 PSI LOW, 5000 PSI HIGH FOR 10 MINUTES EACH. TESTED TOP DRIVE IBOP & BLIND RAMS TO 300 PSI LOW AND 5000 PSI HIGH FOR 10 MINUTES. ANNULAR TESTED TO 300 PSI LOW AND 2500 PSI HIGH FOR 10 MINUTES EACH. KILL LINE LEAKED. REPAIRED & RETESTED. VIBRATOR HOSE AT PUMP LEAKED. REPLACED AND RETESTED. REDUCED PUMP LINER SIZE IN BOTH MUD PUMPS.
	23:30 0:30	1.00	CASSURF	31		P	3,646.0	TESTED CASING TO 2500 PSI FOR >30 MINUTES.
	0:30 4:00	3.50	CASSURF	28		P	3,646.0	NU ROTATING HEAD AND FLOWLINE. INSTALLED WEAR BUSHING
	4:00 6:00	2.00	CASSURF	14		P	3,646.0	PJSM. PUMU & TESTED RYAN'S 1.5 MM/MWD STEERABLE ASSY.
3/24/2013	6:00 8:00	2.00	CASSURF	14		P	3,646.0	PUMU 16 DRILL COLLARS.
	8:00 10:00	2.00	CASSURF	13		P	3,646.0	TIH. INSTALLED RH RUBBER.
	10:00 11:30	1.50	CASSURF	32		P	3,646.0	DRILLED CEMENT & FE. DRILLED 10' NH TO 3,656'.
	11:30 12:30	1.00	DRLINT1	33		P	3,656.0	PERFORMED 13.0 EMW LOT.
	12:30 1:00	12.50	DRLINT1	08		P	3,656.0	DRILLED 3,656' - 4,320'. UTILIZED ONE PUMP DUE TO MODULE REPLACEMENT ON PUMP 1.
	1:00 6:00	5.00	DRLINT1	08		P	4,320.0	DRILLED 4,320' - 4,500'. UTILIZED TWO PUMPS PART-TIME.
3/25/2013	6:00 7:30	1.50	DRLINT1	08		P	4,500.0	DRILLED 4,500'-4,591'.
	7:30 8:00	0.50	DRLINT1	12		P	4,591.0	SERVICED RIG & TDU.
	8:00 6:00	22.00	DRLINT1	08		P	4,591.0	DRILLED 4,591'-6,200'.
3/26/2013	6:00 23:30	17.50	DRLINT1	08		P	6,200.0	DRILLED 6,200-6,822'.

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duratio n (hr)	Phase	Activit y	Sub	OP Code	MD From (ft)	Operation
3/27/2013	23:30 0:00	0.50	DRLINT1	12		P	6,822.0	SERVICED RIG & TDU.
	0:00 6:00	6.00	DRLINT1	08		P	6,822.0	DRILLED 6,822'-7,000'.
	6:00 10:30	4.50	DRLINT1	08		P	7,000.0	DRILLED 7,000'-7,101'.
	10:30 11:00	0.50	DRLINT1	12		P	7,101.0	SERVICED RIG & TDU.
	11:00 1:30	14.50	DRLINT1	08		P	7,101.0	DRILLED 7,101'-7,474'.
	1:30 2:00	0.50	DRLINT1	12		P	7,474.0	SAFETY STAND-DOWN.
3/28/2013	2:00 6:00	4.00	DRLINT1	08		P	7,474.0	DRILLED 7,474'- 7,489'. PLUGGED BIT JETS CLEARED AT 5 AM.
	6:00 7:00	1.00	DRLINT1	07		P	7,489.0	DRILL 7,489' - 7,522'.
	7:00 22:00	15.00	DRLINT1	13		P	7,522.0	POOH FOR NEW BIT AND MOTOR. HOLE SWABBING, FILL W/ TD.
	22:00 0:30	2.50	DRLINT1	13		P	7,522.0	PU & TESTED MM. (FAILURE). PU & TEST BACK UP MM. TEST GOOD. MU BHA.
	0:30 3:30	3.00	DRLINT1	13		P	7,522.0	TIH W/ BIT #3. TO SHOE.
	3:30 5:00	1.50	DRLINT1	12		P	7,522.0	SLIP & CUT DRILLING LINE.
3/29/2013	5:00 6:00	1.00	DRLINT1	13		P	7,522.0	TIH
	6:00 7:00	1.00	DRLINT1	43		N	7,522.0	REPAIR LOW/HIGH SPEED TORQUE VALVE ON TDU.
	7:00 13:30	6.50	DRLINT1	13		P	7,522.0	TIH. WASH IN HOLE FROM 4,000' TO 7,522'.
	13:30 6:00	16.50	DRLINT1	07		P	7,522.0	DRILL 7,522' -8200'.
	6:00 14:30	8.50	DRLINT1	07		P	8,200.0	DRILL 8,200' - 8,503'.
3/30/2013	14:30 15:00	0.50	DRLINT1	12		P	8,503.0	RIG SERVICE.
	15:00 6:00	15.00	DRLINT1	07		P	8,503.0	DRILL 8,503' - 9084'.
	6:00 9:00	3.00	DRLINT1	07		P	9,084.0	DRILL 9,084' - 9,250'.
3/31/2013	9:00 9:30	0.50	DRLINT1	12		P	9,250.0	RIG SERVICE.
	9:30 10:00	0.50	DRLINT1	07		P	9,250.0	DRILL 9,250' - 9,265'.
	10:00 14:30	4.50	DRLINT1	15		P	9,265.0	C&C MUD. RAISE MUD WT. TO 10.6 PPG.
	14:30 23:30	9.00	DRLINT1	13		P	9,265.0	TOH TO SHOE.
	23:30 0:00	0.50	DRLINT1	15		P	9,265.0	C&C MUD
	0:00 5:30	5.50	DRLINT1	13		P	9,265.0	STAGE IN HOLE TO 9270'.
	5:30 6:00	0.50	DRLINT1	15		P	9,265.0	C&C MUD
	6:00 12:30	6.50	DRLINT1	13		P	9,270.0	C&C MUD, CIRCULATE 10.6PPG MUD.
4/1/2013	12:30 0:00	11.50	DRLINT1	14		P	9,270.0	LD DRILL STRING.
	0:00 2:00	2.00	DRLINT1	13		P	9,270.0	LD DC'S RYAN TOOLS
	2:00 2:30	0.50	DRLINT1	42		P	9,270.0	PULL WEAR BUSHING.
	2:30 6:00	3.50	EVLINT1	22		P	9,270.0	PJSM WITH HALLIBURTON AND PRECISION. RIG UP HALLIBURTON WIRELINE AND LOG. RUN QUAD COMBO WITH SONIC.
	6:00 7:30	1.50	EVLINT1	22		P	9,270.0	LOG 8 3/4 SECTION. LOGGERS DEPTH 9,280'.
4/2/2013	7:30 8:00	0.50	CASINT1	24		P	9,270.0	CHANGE OUT ELEVATORS AND BALES.
	8:00 1:30	17.50	CASINT1	24		P	9,270.0	SM. RU AND RUN 226 JTS, OF 7", 29#, HCP-110 CASING. LENGTH: 9,270'. LAND AT 9,263'. LD FILL TOOL. PU LANDING JT. AND LAND MANDREL.
	1:30 3:30	2.00	CASINT1	15		P	9,270.0	RU CIRC. SWEDGE, C&C MUD. RIG DOWN FRANK'S WESTATES AND RIG UP HALLIBURTON CEMENTERS.
	3:30 6:00	2.50	CASINT1	25		P	9,270.0	PJSM WITH HALLIBURTON. INSTALL CEMENT HEAD. PRESSURE TEST CEMENT LINES TO 5000 PSI. CEMENT 7" CASING.
	6:00 7:00	1.00	CASINT1	25		P	9,270.0	CEMENT 7" CSG WITH 50 BBLS. FRESH WATER SPACER, 145 BBLS (367 SKS, 12.0#/GAL, YIELD 2.28, 12.83 GAL/SK WATER) LEAD CEMENT. 33 BBLS (95 SKS., 12.5#/GAL, YIELD 1.92, 10.37 GAL/SK WATER.) TAIL. SHUT DOWN, WASH LINES,DROP PLUG. DISPLACED WITH 342 BBLS 10.3 PPG DRILLING MUD. BUMPED PLUG AT 500 PSI OVER. FLOAT HELD, FLOWED BACK 1.5 BBLS. FULL RETURNS THROUGHOUT JOB. TOP OF CEMENT AT 3,100'. RD CEMENTERS.



## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD From (ft)	Operation
4/4/2013	7:00 10:00	3.00	CASINT1	42		P	9,270.0	LAY DOWN 4 1/2" HANDLING TOOLS. PICK UP 3 1/2" HANDLING TOOLS. CHANGE TOP DRIVE SUB. INSTALL BALES AND ELEVATORS.
	10:00 11:30	1.50	CASINT1	27		P	9,270.0	INSTALL PACK-OFF AND TEST.
	11:30 22:00	10.50	CASINT1	30		P	9,270.0	SET TEST PLUG AND TEST BOPE. 250PSI LOW, 10000PSI HIGH. TEST BLIND RAMS. PIPE RAMS DID NOT TEST. TEST TOP DRIVE, SAFETY VALVES. REPLACED SEAL ON HCR VALVE, AND TEST. CHANGED OUT VARIABLE PIPE RAMS AND TEST. TEST ANNULAR 250PSI LOW, 4000PSI HIGH.
	22:00 23:00	1.00	CASINT1	31		P	9,270.0	TEST CASING TO 2500 PSI, 30 MINUTES. RD TESTER.
	23:00 6:00	7.00	CASINT1	14		P	9,270.0	PU 6 1/8" BHA AND 3 1/2" DP.
	6:00 10:00	4.00	CASINT1	14		P	9,270.0	PICK UP 3-1/2" DRILL PIPE
	10:00 11:30	1.50	CASINT1	17		P	9,270.0	SLIP AND CUT DRILLING LINE
	11:30 13:00	1.50	CASINT1	32		P	9,270.0	PICK UP 3-1/2" DRILL PIPE. TAG CEMENT AT 9,235'. DRILLING FLOAT COLLAR, CEMENT, AND FLOAT SHOE TO 9280'. 10' OF NEW HOLE.
	13:00 13:30	0.50	DRLPRD	15		P	9,280.0	CIRCULATE BOTTOMS UP FOR FIT.
	13:30 14:00	0.50	DRLPRD	33		P	9,280.0	PERFORM F.I.T. 10.3 MUD WEIGHT WITH 2,452 ADDED SURFACE PRESSURE FOR AN EMW OF 15.4 PPG. BLOW OUT CHOKE LINE.
4/5/2013	14:00 15:00	1.00	DRLPRD	07		P	9,280.0	DRILLING FROM 9,280' TO 9,366'.
	15:00 15:30	0.50	DRLPRD	12		P	9,366.0	RIG SERVICE.
	15:30 6:00	14.50	DRLPRD	07		P	9,366.0	DRILLING FROM 9,366' - 9,972'.
	6:00 9:30	3.50	DRLPRD	07		P	9,972.0	DRILLING FROM 9972' TO 10,177'. RAISE MUD WEIGHT FROM 10.6PPG TO 11.2 PPG.
	9:30 15:30	6.00	DRLPRD	50		P	10,177.0	SHUT WELL IN. MONITOR PRESSURES. CIRCULATE GAS OUT THROUGH CHOKE. RAISE MUD WEIGHT FROM 11.2 PPG TO 12.3 PPG.
	15:30 6:00	14.50	DRLPRD	07		P	10,177.0	DRILLING FROM 10,177' TO 10,720'. RAISING MUD WEIGHT FROM 12.3 PPG TO 13.3 PPG.

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> Fee
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> EP ENERGY E&P COMPANY, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1001 Louisiana, Houston, TX, 77002		<b>8. WELL NAME and NUMBER:</b> Taylor 3-9C4
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0900 FSL 1750 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWSE Section: 09 Township: 03.0S Range: 04.0W Meridian: U		<b>9. API NUMBER:</b> 43013519540000
<b>PHONE NUMBER:</b> 713 997-5038 Ext		<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: <b>4/29/2013</b>  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input checked="" type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION         </div> </div>	
OTHER: <input type="text" value="Initial Completion"/>		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. EP plans to complete to Wasatch. Please see attached for details.		
<p style="color: red; margin: 0;"> <b>Approved by the              Utah Division of              Oil, Gas and Mining</b> </p> <p style="margin: 0;"> <b>Date:</b> April 25, 2013         </p> <p style="margin: 0;"> <b>By:</b> <u><i>Derek Duff</i></u> </p>		
<b>NAME (PLEASE PRINT)</b> Maria S. Gomez	<b>PHONE NUMBER</b> 713 997-5038	<b>TITLE</b> Principal Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 4/23/2013	

**Taylor 3-9C4  
Initial Completion  
43013519540000**

**The following precautions will be taken until the RCA for the Conover is completed:**

1. Review torque turning and running of the 7" and 5" liner of anomalies.
2. Test and chart casing for 30 minutes, noting pressure if any on surface casing.
3. Test all lubricators, valves and BOP's to working pressure.
4. Wellhead isolation tools will continue to be used to isolate the wellhead during the frac.
5. Monitor the surface casing during frac:
  - a. Lay a flowline to the flow back tank and keep the valve open.
  - b. This line will remain in place until a wire line set retrievable packer is in place isolating the 5" casing from the 7" after the frac.
6. 2 7/8" tubing will be run to isolate the 7" casing during the flow back of the well.
7. Well pressure and annulus pressure would be monitored during this time until the well is ready for pump.

**Completion Information (Wasatch Formation)**

- |          |   |
|----------|---|
| Stage 1: | RU WL unit with 10K lubricator and test to 10000 psi with glycol. Perforations from ~11494' – 11858' with ~5000 gallons of 15% HCL acid, ~3000# of 100 mesh sand and ~140000# Powerprop 20/40.                    |
| Stage 2: | RU 10K lubricator and test to 10000 psi with glycol. Set 10K CBP @ ~11450'. Tag CBP. Perforations from ~11074' – 11444' with ~5000 gallons of 15% HCL acid, ~3000# of 100 mesh sand and ~115000# Powerprop 20/40. |
| Stage 3: | RU 10K lubricator and test to 10000 psi with glycol. Set 10K CBP @ ~11050'. Tag CBP. Perforations from ~10760' – 11043' with ~5000 gallons of 15% HCL acid, ~3000# of 100 mesh sand and ~155000# Powerprop 20/40. |


- Stage 4: RU 10K lubricator and test to 10000 psi with glycol. Set 10K CBP @ ~10745'. Tag CBP. Perforations from ~10418' – 10736' with ~5000 gallons of 15% HCL acid, ~3000# of 100 mesh sand and ~155000# Powerprop 20/40.
- Stage 5: RU 10K lubricator and test to 10000 psi with glycol. Set 10K CBP @ ~10405'. Tag CBP. Perforations from ~10139' – 10394' with ~5000 gallons of 15% HCL acid, ~3000# of 100 mesh sand and ~155000# Powerprop 20/40.
- Stage 6: RU 10K lubricator and test to 10000 psi with glycol. Set 10K CBP @ ~10115'. Tag CBP. Perforations from ~9896' – 10109' with ~5000 gallons of 15% HCL acid, ~3000# of 100 mesh sand and ~140000# Powerprop 20/40.
- Stage 7: RU 10K lubricator and test to 10000 psi with glycol. Set 10K CBP @ ~9870'. Tag CBP. Perforations from ~9622' – 9864' with ~5000 gallons of 15% HCL acid, ~3000# of 100 mesh sand and ~140000# TLC 20/40.
- Stage 8: RU 10K lubricator and test to 10000 psi with glycol. Set 10K CBP @ ~9610'. Tag CBP. Perforations from ~9311' – 9592' with ~5000 gallons of 15% HCL acid, ~3000# of 100 mesh sand and ~140000# TLC 20/40.



**Initial Completion Wellbore Schematic**

Company Name: EP Energy  
Well Name: **Taylor 3-9C4**  
Field, County, State: Altamont - Bluebell, Duchesne, Utah  
Surface Location: Lat: 40° 13' 48.87713" N Long: 110° 20' 17.45761" W  
Producing Zone(s): Wasatch

Last Updated: 4/19/2013  
By: Peter Schmeltz  
TD: 12,000'  
BHL: \_\_\_\_\_  
Elevation: \_\_\_\_\_





Current Wellbore Schematic

Company Name: EP Energy

Well Name: Taylor 3-9C4

Field, County, State: Altamont - Bluebell, Duchesne, Utah

Surface Location: Lat: 40° 13' 48.87713" N Long: 110° 20' 17.45761" W

Producing Zone(s): Wasatch

Last Updated: 4/10/2013

By: Peter Schmeltz

TD: 12,000'

BHL: \_\_\_\_\_

Elevation: \_\_\_\_\_

8.43 ppg KCL water in the wellbore

9-5/8" 40# N-80 LTC @ 3,640' MD

TOC @ XXX'

TOL @ 9,030'

7" 29# HCP-110 LTC @ Surface-9,271' MD  
Drift I.D. - 6.059"

LC @ 11,904'  
FC @ 11,951'  
FS @ 11,997'

5" 18# P-110 STL @ 11,997' MD  
Drift ID 4.151"

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> Fee
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> EP ENERGY E&P COMPANY, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1001 Louisiana , Houston, TX, 77002		<b>8. WELL NAME and NUMBER:</b> Taylor 3-9C4
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0900 FSL 1750 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWSE Section: 09 Township: 03.0S Range: 04.0W Meridian: U		<b>9. API NUMBER:</b> 43013519540000
<b>PHONE NUMBER:</b> 713 997-5038 Ext		<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 4/5/2015	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input checked="" type="checkbox"/> OTHER	
	OTHER: <input type="text" value="See below"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Downsize & deepen to convert to corod. See attached for details.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> May 26, 2015		
<b>NAME (PLEASE PRINT)</b> Maria S. Gomez	<b>PHONE NUMBER</b> 713 997-5038	<b>TITLE</b> Principal Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 5/25/2015	

## CENTRAL DIVISION

ALTAMONT FIELD  
TAYLOR 3-9C4  
TAYLOR 3-9C4  
WORKOVER LAND

### Operation Summary Report

Disclaimer: Although the information contained in this report is based on sound engineering practices, the copyright owner(s) does (do) not accept any responsibility whatsoever, in negligence or otherwise, for any loss or damage arising from the possession or use of the report whether in terms of correctness or otherwise. The application, therefore, by the user of this report or any part thereof, is solely at the user's own risk.



## 1 General

### 1.1 Customer Information

Company	CENTRAL DIVISION
Representative	
Address	

### 1.2 Well Information

Well	TAYLOR 3-9C4		
Project	ALTAMONT FIELD	Site	TAYLOR 3-9C4
Rig Name/No.	NABORS DRILLING/0561	Event	WORKOVER LAND
Start date	3/31/2015	End date	4/4/2015
Spud Date/Time	3/18/2013	UWI	TAYLOR 3-9C4
Active datum	KB @6,016.1ft (above Mean Sea Level)		
Afe No./Description	164477/53677 / TAYLOR 3-9C4		

## 2 Summary

### 2.1 Operation Summary

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
4/1/2015	10:00 13:00	3.00	MIRU	01		P		MOVE FROM 2-19C4, HSM, SLIDING ROTAFLEX SLIDE ROTAFLEX BACK, SPOT & RIG UP HOT OILER R/U TO CSG PUMP 150 BBLs 2% KCL @ 200 DEG
	13:00 15:00	2.00	WOR	18		P		L/D POLISH ROD & 2' PONY ROD, P/U 1" WORK ROD, ATTEMPT TO UNSEAT PUMP, NO LUCK, BACK OFF RODS
	15:00 18:00	3.00	WLWORK	39		P		POOH L/D ROD STRING W/ 97-1" EL RODS W/G 117-7/8" EL RODS W/G 4-3/4" EL RODS W/G X/O TO TBG EQUIP TBG SHUT IN, CSG SALES, SDFN.  2% KCL PUMPED = 200 DIESEL USED = 64 GAL PROPANE USED = 225
4/2/2015	6:00 7:30	1.50	WBP	28		P		TRAVEL TO LOCATION, HSM, R/U WIRELINE 100# SITP & FCP, BLEED OFF HOT OILER PUMP 100 BBLs 2% KCL @ 200 DEG DOWN CSG
	7:30 8:30	1.00	WLWORK	21		P		MIRU THE PERFORATORS, RIH W/ 1 9/16" TBG PUNCH LOADED 4 SPF, TAG @ 5515' WLD, P/U PERF TBG 5490'-5491', POOH R/D WIRELINE
	8:30 10:00	1.50	WOR	16		P		REMOVE CAPSTRING ASSEMBLY, N/D WH, UNLAND TBG REMOVE B-FLANGE, INSTALL 6' TBG SUB & HANGER, LAND ON HANGER, N/U BOPS, R/U FLOOR & TBG EQUIP, RELEASE TAC.
	10:00 11:30	1.50	WOR	39		P		POOH W/ 167 JTS 2 7/8" N-80 TBG, 1 JT 2 7/8" N-80 TBG( PERFORATED, 1 JT 2 7/8" N-80 TBG TO RODS, X/O TO ROD EQUIP
	11:30 13:00	1.50	WOR	39		P		ATTEMPT TO UNSEAT PUMP, UNABLE TO WORK OFF SEAT, BACK OFF RODS, POOH W/ 113-3/4" EL RODS, 2-1 1/2" K-BARS X/O TO TBG

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
	13:00 19:00	6.00	WOR	39		P		<p>POOH W/ 87 JTS 2 7/8" N-80 TBG, TO RODS, CONT STRIPPING OOH W/ 9 JTS 2 7/8" N-80 TBG, 7" TAC, 4 JTS 2 7/8" N-80 TBG, 4' 2 7/8" TBG SUB, 2 7/8" SN, 2'-2 7/8" TBG SUB, 5 1/2" PBGA, 2 JTS 2 7/8" N-80 TBG, 5 3/4" SOLID NO-GO 17-1 1/2" KARS &amp; PUMP, MAKING SEVERAL BACK OFFS. TAC HANGING UP W/ 20 JTS LEFT IN HOLE, HAD TO WORK FREE SEVERAL TIMES WHILE POOH.( CAGE FROM TAC WAS MISSING, FELL TO PBGA, RETRIEVED CAGE, MISSING 2 SLIPS &amp; SET OF DRAG SPRINGS ) TBG SHUT IN, CSG TO SALES, SDFN.</p> <p>2% KCL PUMPED = 330 BBLS DIESEL USED = 88 GAL PROPANE USED = 275 GAL</p>
4/3/2015	7:00 8:30	1.50	WOR	28		P		<p>TRAVEL TO LOCATION, HSM, TRIPPING IN HOLE W/ TUBING FCP = 200# BLEED OFF ( NOTE = NABORS HAD CO. SAFETY MTG. ) HOT OILER PUMP 50 BBLS 2% KCL @ 200 DEG DOWN CSG</p>
	8:30 10:00	1.50	WOR	32		P		<p>RIH W/ WL REENTRY GUIDE, 1 JT 2 7/8" N-80 TBG, 6'-2 7/8" N-80 TBG SUB, CLOSE PIPE RAMS, MIRU DELSCO SLICKLINE UNIT, RIH W/ 1 1/2" SINKER BARS, TAG @ 11881' WLD, POOH R/D SL UNIT.</p>
	10:00 15:00	5.00	WOR	39		P		<p>P/U &amp; RIH W/ 2 3/8" BULL PLUG, 2 JTS 2 3/8" N-80 TBG, 2 3/8" # 3 DESANDER, 4'-2 3/8" N-80 TBG SUB, 2 3/8" SEAT NIPPLE, 4 JTS 2 3/8" N-80 TBG, 5" TAC, 70 JTS 2 3/8" N-80 TBG, 2 7/8" X 2 3/8" EUE X/O SUB, 270 JTS 2 7/8" N-80 TBG, 6' TBG SUB &amp; HANGER, SET TAC @ 10882.18' W/ 25K TENSION. LAND ON HANGER</p> <p>TUBING DETAIL KB = 17.00' TUBING STRETCH = 5.00' 273 JTS 2 7/8" N-80 TUBING = 8899.04' 2 7/8" X 2 3/8" X-OVER = .80' 61 JTS 2 3/8" N-80 TBG = 1960.34' 5" TAC W/ CARB SLIPS = 3.09' 4 JTS 2 3/8" N-80 TUBING = 128.70' 2 3/8" +45 SEAT NIPPLE = 1.10' 4' - 2 3/8" N-80 TUBING SUB = 4.14' 2 3/8" #3 CAVINS DESANDER = 19.23' 2 JTS 2 3/8" N-80 TBG ( MUD JOINTS ) = 64.09' 2 3/8" BULL PLUG = .68'</p> <p>----- EOT @ 11103.21'</p> <p>5" TAC @ 10882.18' 2 3/8" SEAT NIPPLE @ 11013.97'</p>

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
	15:00 17:00	2.00	WOR	16		P		R/D FLOOR & TBG EQUIP, N/D BOPS, UNALND TBG, REMOVE TBG SUB & HANGER INSTALL B-FLANGE, LAND ON B-FLANGE, N/U WH, INSTALL CAP STRING. TBG SHUT IN CSG TO SALES, RDMO, SDFN  2% KCL PUMPED = 50 BBLS DIESEL USED = 80 GAL PROPANE USED = 25 GAL
4/4/2015	6:00 7:30	1.50	WBP	28		P		TRAVEL TO LOCATION, HSM, RIGGING UP CO-ROD RIG 100# SITP & FCP, BLEED OFF HOT OILER FLUSH TBG W/ 70 BBLS 2% KCL @ 200 DEG, SPOT 10 GAL CORROSION INHIBITOR
	7:30 13:00	5.50	INARTLT	03		P		P/U & PRIME WALS 2" X 1 1/2" X 38' RHBC PUMP RIH W/ 3'- 3/4" STABILIZER SUB, ON/OFF TOOL 1360'-16/16" SE CO-ROD 6191'-15/16" SE CO-ROD, MAKE WELD TO 1251'-16/16" SE CO-ROD 1088'- 17/16" SE CO-ROD 1065'-18/16" SE CO-ROD, WELD ON TOP PIN SPACE W/ 1" EL PNY RODS = 1-4', 1-6', 1-8' P/U NEW 1 1/2" X 40' POLISH ROD, HANG OFF
	13:00 13:30	0.50	INARTLT	18		P		HOT OILER FILL TBG W/ 30 BBLS 2% KCL, PSI TEST TO 500#, STROKE TEST TO 1000# , GOOD TEST, PSI TES CV TO 1000#, GOOD, PUMP 15 BBLS 2% KCL @ 200 DEG ACROSS FLOWLINE.
	13:30 14:30	1.00	RDMO	02		P		RDMO, SLIDE ROTAFLEX IN, CHECK PUMP, NO TAG, GOOD PUMP ACTION, TWOTO.  2% KCL PUMPED = 250 BBLS DIESEL USED = 36 GAL PROPANE USED = 150 GAL

Table of Contents

1	General.....	1
1.1	Customer Information.....	1
1.2	Well Information.....	1
2	Summary.....	1
2.1	Operation Summary.....	1

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:	
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
2. NAME OF OPERATOR: EP Energy E&P Company, L.P.		7. UNIT or CA AGREEMENT NAME	
3. ADDRESS OF OPERATOR: 1001 Louisiana CITY Houston STATE TX ZIP 77002		8. WELL NAME and NUMBER: Taylor 3-9C4	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 900 FSL & 1750 FEL AT TOP PRODUCING INTERVAL REPORTED BELOW: 900 FSL & 1750 FEL AT TOTAL DEPTH: 900 FSL & 1750 FEL		9. API NUMBER: 4301351954	
		10 FIELD AND POOL, OR WILDCAT Altamont	
		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 9 3S 4W U	
		12. COUNTY Duchesne	13. STATE UTAH

14. DATE SPUNDED: 3/17/2013	15. DATE T.D. REACHED: 4/6/2013	16. DATE COMPLETED: 5/1/2013	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL):
18. TOTAL DEPTH: MD 11,997 TVD 11,997	19. PLUG BACK T.D.: MD TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *	21. DEPTH BRIDGE MD PLUG SET: TVD	
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) Sonic, Gamma Ray, Resistivity & Neutron Density			23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input type="checkbox"/> YES <input checked="" type="checkbox"/> (Submit copy)	

### 24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
17.5	13.375 J55	54.5	0	610		G 763	877	0	
12.25	9.625 N80	40	0	3,640		G 825	2,064	0	
8.75	7" HCP	29	0	9,271		G 458	1,022	6234 *	
6.125	5 P110	18	8,994	11,997		172	253	8994	

### 25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2.875	8,957	8860						

### 26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) Wasatch	9,291	11,858	9,291	11,858	11,494 11,858	.43	69	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B)					11,074 11,444	.43	69	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(C)					10,760 11,043	.43	60	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(D)					10,418 10,736	.43	69	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>

### 27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC. See attached for further information on #27 & #28.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
11494-11858	5000 gal 15% HCL, 3000# 100 Mesh, 140960# 20/40 Power Prop
11074-11444	5000 gal 15% HCL, 3000# 100 Mesh, 115540# 20/40 Power Prop
10760-11043	5000 gal 15% HCL, 3000# 100 Mesh, 156300# 20/40 Power Prop

29. ENCLOSED ATTACHMENTS: All logs are submitted to UDOGM by vendor.

30. WELL STATUS:

- |   |  |                                       |   |
|---|--|---------------------------------------|---|
| <input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS                         | <input type="checkbox"/> GEOLOGIC REPORT | <input type="checkbox"/> DST REPORT   | <input type="checkbox"/> DIRECTIONAL SURVEY |
| <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION | <input type="checkbox"/> CORE ANALYSIS   | <input type="checkbox"/> OTHER: _____ |   |



## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 5/3/2013	TEST DATE: 5/13/2013	HOURS TESTED: 24	TEST PRODUCTION RATES: →	OIL – BBL: 479	GAS – MCF: 589	WATER – BBL: 721	PROD. METHOD: Rod Pump
CHOKE SIZE: 16	TBG. PRESS. 1,994	CSG. PRESS. 44.40	API GRAVITY 1	BTU – GAS 1	GAS/OIL RATIO 1	24 HR PRODUCTION RATES: →	INTERVAL STATUS: Prod

## INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

Sold

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				Upper Green River	4,438
				Middle Green River	6,150
				Lower Green River	7,455
				Wasatch	9,291

## 35. ADDITIONAL REMARKS (Include plugging procedure)

## 36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Maria S. Gomez

TITLE Principal Regulatory Analyst

SIGNATURE

Maria S. Gomez

DATE

12/19/13

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

**Attachment to Well Completion Report****Form 8 Dated December 17, 2013****Well Name: Taylor 3-9C4****Items #27 and #28 Continued****27. Perforation Record**

<b>Interval (Top/Bottom – MD)</b>	<b>Size</b>	<b>No. of Holes</b>	<b>Perf. Status</b>
<b>10139'-10394'</b>	<b>43</b>	<b>69</b>	<b>Open</b>
<b>9896'-10109'</b>	<b>43</b>	<b>69</b>	<b>Open</b>
<b>9622'-9864'</b>	<b>43</b>	<b>69</b>	<b>Open</b>
<b>9311'-9592'</b>	<b>43</b>	<b>69</b>	<b>Open</b>

**28. Acid, Fracture, Treatment, Cement Squeeze, Etc.**

<b>Depth Interval</b>	<b>Amount and Type of Material</b>
<b>10418'-10736'</b>	<b>5000 gal 15% HCL, 3000# 100 mesh, 154580# 20/40 Power Prop</b>
<b>10139'-10394'</b>	<b>5000 gal 15% HCL, 3000# 100 Mesh, 155160# 20/40 Power Prop</b>
<b>9896'-10109'</b>	<b>5000 gal 15% HCL, 3000# 100 Mesh, 137900# 20/40 Power Prop</b>
<b>9622'-9864'</b>	<b>5000 gal 15% HCL, 3000# 100 mesh, 140000# 20/40 Tempered LC</b>
<b>9311'-9592'</b>	<b>5000 gal 15% HCL, 3000# 100 Mesh, 140160# 20/40 Tempered LC</b>

**\*3390'-6234' Poor cmt**



<b>Company:</b>	EP Energy	<b>Job Number:</b>		<b>Calculation Method</b>	Minimum Curvature
<b>Well:</b>	Taylor 3-9 C4	<b>Mag Decl.:</b>		<b>Proposed Azimuth</b>	0.00
<b>Location:</b>	Duchesne, UT	<b>Dir Driller:</b>		<b>Depth Reference</b>	KB
<b>Rig:</b>	Precision 406	<b>MWD Eng:</b>		<b>Tie Into:</b>	Gyro/MWD

Survey Number	Survey Depth (ft)	Inclination (deg)	Azimuth (deg)	Course Length (ft)	True Vertical Depth (ft)	Vertical Section (ft)	Coordinates		Closure		Dogleg Severity (d/100')	Build Rate (d/100')	Walk Rate (d/100')
							N/S (ft)	E/W (ft)	Distance (ft)	Direction Azimuth			
<b>Tie In</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>										
1	100.00	0.35	134.58	100.00	100.00	-0.21	0.21 S	0.22 E	0.31	134.58	0.35	0.35	134.58
2	200.00	0.39	126.21	100.00	200.00	-0.63	0.63 S	0.71 E	0.95	131.59	0.07	0.04	-8.37
3	300.00	0.44	119.82	100.00	299.99	-1.02	1.02 S	1.32 E	1.67	127.80	0.07	0.05	-6.39
4	400.00	0.30	117.65	100.00	399.99	-1.33	1.33 S	1.88 E	2.31	125.33	0.14	-0.14	-2.17
5	500.00	0.51	115.46	100.00	499.99	-1.65	1.65 S	2.52 E	3.01	123.21	0.21	0.21	-2.19
6	675.00	0.48	80.16	175.00	674.98	-1.86	1.86 S	3.94 E	4.36	115.22	0.17	-0.02	-20.17
7	768.00	1.10	32.17	93.00	767.98	-1.03	1.03 S	4.80 E	4.91	102.16	0.92	0.67	-51.60
8	862.00	2.02	4.97	94.00	861.94	1.38	1.38 N	5.42 E	5.60	75.73	1.23	0.98	-28.94
9	955.00	3.21	353.67	93.00	954.84	5.60	5.60 N	5.28 E	7.70	43.31	1.39	1.28	374.95
10	1048.00	2.99	355.65	93.00	1047.71	10.61	10.61 N	4.81 E	11.65	24.39	0.26	-0.24	2.13
11	1141.00	2.90	355.87	93.00	1140.58	15.37	15.37 N	4.46 E	16.00	16.16	0.10	-0.10	0.24
12	1235.00	2.99	356.26	94.00	1234.46	20.19	20.19 N	4.12 E	20.61	11.54	0.10	0.10	0.41
13	1328.00	2.81	353.45	93.00	1327.34	24.88	24.88 N	3.71 E	25.15	8.47	0.25	-0.19	-3.02
14	1421.00	3.78	350.33	93.00	1420.19	30.16	30.16 N	2.93 E	30.30	5.55	1.06	1.04	-3.35
15	1514.00	3.78	352.05	93.00	1512.98	36.22	36.22 N	1.99 E	36.28	3.15	0.12	0.00	1.85
16	1608.00	3.78	350.95	94.00	1606.78	42.35	42.35 N	1.08 E	42.36	1.46	0.08	0.00	-1.17
17	1701.00	4.00	350.33	93.00	1699.56	48.57	48.57 N	0.05 E	48.57	0.06	0.24	0.24	-0.67
18	1794.00	3.30	358.46	93.00	1792.38	54.45	54.45 N	0.57 W	54.45	359.40	0.93	-0.75	8.74
19	1887.00	2.90	0.35	93.00	1885.24	59.48	59.48 N	0.63 W	59.48	359.40	0.44	-0.43	-385.06
20	1979.00	3.52	356.44	92.00	1977.09	64.62	64.62 N	0.79 W	64.63	359.30	0.71	0.67	387.05
21	2072.00	3.38	351.87	93.00	2069.93	70.19	70.19 N	1.35 W	70.20	358.90	0.33	-0.15	-4.91
22	2164.00	3.30	358.86	92.00	2161.77	75.52	75.52 N	1.79 W	75.54	358.64	0.45	-0.09	7.60
23	2257.00	3.21	359.56	93.00	2254.62	80.80	80.80 N	1.86 W	80.82	358.68	0.11	-0.10	0.75
24	2350.00	2.90	359.34	93.00	2347.49	85.75	85.75 N	1.91 W	85.77	358.73	0.33	-0.33	-0.24
25	2442.00	2.99	353.94	92.00	2439.37	90.47	90.47 N	2.19 W	90.49	358.61	0.32	0.10	-5.87
26	2535.00	2.59	355.56	93.00	2532.26	94.97	94.97 N	2.61 W	95.01	358.43	0.44	-0.43	1.74
27	2628.00	2.59	352.75	93.00	2625.16	99.15	99.15 N	3.03 W	99.20	358.25	0.14	0.00	-3.02
28	2721.00	2.42	347.04	93.00	2718.07	103.15	103.15 N	3.74 W	103.22	357.92	0.32	-0.18	-6.14
29	2813.00	2.20	350.46	92.00	2810.00	106.79	106.79 N	4.47 W	106.88	357.60	0.28	-0.24	3.72
30	2906.00	2.90	352.97	93.00	2902.91	110.88	110.88 N	5.05 W	111.00	357.39	0.76	0.75	2.70
31	2999.00	2.90	356.84	93.00	2995.79	115.56	115.56 N	5.47 W	115.69	357.29	0.21	0.00	4.16
32	3092.00	2.68	352.75	93.00	3088.68	120.07	120.07 N	5.87 W	120.21	357.20	0.32	-0.24	-4.40
33	3184.00	2.50	353.85	92.00	3180.58	124.20	124.20 N	6.36 W	124.36	357.07	0.20	-0.20	1.20
34	3277.00	2.20	350.77	93.00	3273.50	127.98	127.98 N	6.86 W	128.16	356.93	0.35	-0.32	-3.31
35	3369.00	1.89	344.05	92.00	3365.44	131.18	131.18 N	7.56 W	131.40	356.70	0.43	-0.34	-7.30





<b>Company:</b>	EP Energy	<b>Job Number:</b>		<b>Calculation Method</b>	Minimum Curvature
<b>Well:</b>	Taylor 3-9 C4	<b>Mag Decl.:</b>		<b>Proposed Azimuth</b>	0.00
<b>Location:</b>	Duchesne, UT	<b>Dir Driller:</b>		<b>Depth Reference</b>	KB
<b>Rig:</b>	Precision 406	<b>MWD Eng:</b>		<b>Tie Into:</b>	Gyro/MWD

Survey Number	Survey Depth (ft)	Inclination (deg)	Azimuth (deg)	Course Length (ft)	True Vertical Depth (ft)	Vertical Section (ft)	Coordinates		Closure Distance (ft)	Closure Direction Azimuth	Dogleg Severity (d/100')	Build Rate (d/100')	Walk Rate (d/100')
							N/S (ft)	E/W (ft)					
36	3462.00	1.19	358.46	93.00	3458.41	133.62	133.62 N	8.01 W	133.86	356.57	0.85	-0.75	15.49
37	3554.00	0.79	85.65	92.00	3550.40	134.62	134.62 N	7.40 W	134.83	356.85	1.52	-0.43	-296.53
38	3585.00	0.70	105.86	31.00	3581.40	134.59	134.59 N	7.01 W	134.77	357.02	0.89	-0.29	65.19
39	3696.00	0.48	67.15	111.00	3692.39	134.58	134.58 N	5.93 W	134.71	357.48	0.40	-0.20	-34.87
40	3789.00	0.31	41.26	93.00	3785.39	134.92	134.92 N	5.40 W	135.03	357.71	0.26	-0.18	-27.84
41	3882.00	0.09	122.43	93.00	3878.39	135.07	135.07 N	5.18 W	135.17	357.81	0.33	-0.24	87.28
42	3975.00	0.48	131.35	93.00	3971.39	134.78	134.78 N	4.82 W	134.86	357.95	0.42	0.42	9.59
43	4068.00	0.79	164.97	93.00	4064.38	133.90	133.90 N	4.36 W	133.97	358.13	0.51	0.33	36.15
44	4162.00	0.79	184.35	94.00	4158.37	132.63	132.63 N	4.24 W	132.70	358.17	0.28	0.00	20.62
45	4255.00	1.10	194.24	93.00	4251.36	131.12	131.12 N	4.51 W	131.20	358.03	0.38	0.33	10.63
46	4348.00	0.79	325.37	93.00	4344.36	130.79	130.79 N	5.10 W	130.88	357.77	1.86	-0.33	141.00
47	4441.00	0.31	325.63	93.00	4437.35	131.52	131.52 N	5.60 W	131.64	357.56	0.52	-0.52	0.28
48	4535.00	1.80	355.87	94.00	4531.33	133.20	133.20 N	5.85 W	133.33	357.48	1.64	1.59	32.17
49	4628.00	1.10	345.23	93.00	4624.30	135.52	135.52 N	6.19 W	135.66	357.39	0.80	-0.75	-11.44
50	4721.00	0.62	325.94	93.00	4717.29	136.80	136.80 N	6.70 W	136.97	357.20	0.60	-0.52	-20.74
51	4815.00	1.01	357.54	94.00	4811.28	138.05	138.05 N	7.02 W	138.23	357.09	0.62	0.41	33.62
52	4908.00	0.22	329.55	93.00	4904.28	139.02	139.02 N	7.14 W	139.21	357.06	0.88	-0.85	-30.10
53	5001.00	0.48	59.85	93.00	4997.28	139.37	139.37 N	6.90 W	139.54	357.17	0.57	0.28	-290.00
54	5094.00	0.70	174.16	93.00	5090.27	139.00	139.00 N	6.50 W	139.16	357.32	1.07	0.24	122.91
55	5188.00	0.40	122.74	94.00	5184.27	138.26	138.26 N	6.17 W	138.39	357.45	0.58	-0.32	-54.70
56	5281.00	0.62	173.85	93.00	5277.27	137.58	137.58 N	5.84 W	137.70	357.57	0.52	0.24	54.96
57	5374.00	1.19	170.95	93.00	5370.25	136.13	136.13 N	5.63 W	136.24	357.63	0.61	0.61	-3.12
58	5467.00	0.22	123.97	93.00	5463.25	135.07	135.07 N	5.33 W	135.18	357.74	1.13	-1.04	-50.52
59	5561.00	0.70	200.57	94.00	5557.24	134.43	134.43 N	5.39 W	134.54	357.71	0.73	0.51	81.49
60	5654.00	1.19	178.15	93.00	5650.23	132.94	132.94 N	5.55 W	133.05	357.61	0.65	0.53	-24.11
61	5747.00	0.70	143.04	93.00	5743.22	131.52	131.52 N	5.18 W	131.62	357.74	0.79	-0.53	-37.75
62	5840.00	0.48	54.54	93.00	5836.22	131.29	131.29 N	4.52 W	131.37	358.03	0.90	-0.24	-95.16
63	5933.00	0.88	41.97	93.00	5929.21	132.05	132.05 N	3.73 W	132.10	358.38	0.46	0.43	-13.52
64	6027.00	0.31	23.16	94.00	6023.20	132.82	132.82 N	3.14 W	132.85	358.64	0.63	-0.61	-20.01
65	6120.00	0.09	11.65	93.00	6116.20	133.12	133.12 N	3.03 W	133.16	358.70	0.24	-0.24	-12.38
66	6213.00	1.10	16.74	93.00	6209.20	134.05	134.05 N	2.76 W	134.08	358.82	1.09	1.09	5.47
67	6306.00	1.32	24.57	93.00	6302.18	135.88	135.88 N	2.06 W	135.89	359.13	0.30	0.24	8.42
68	6400.00	0.31	6.55	94.00	6396.16	137.11	137.11 N	1.58 W	137.12	359.34	1.10	-1.07	-19.17
69	6493.00	0.09	212.56	93.00	6489.16	137.30	137.30 N	1.59 W	137.31	359.34	0.42	-0.24	221.52
70	6586.00	0.62	108.37	93.00	6582.16	137.08	137.08 N	1.15 W	137.09	359.52	0.70	0.57	-112.03
71	6679.00	0.88	133.86	93.00	6675.15	136.43	136.43 N	0.16 W	136.43	359.93	0.45	0.28	27.41
72	6772.00	0.40	121.33	93.00	6768.15	135.76	135.76 N	0.64 E	135.77	0.27	0.53	-0.52	-13.47



<b>Company:</b>	EP Energy	<b>Job Number:</b>		<b>Calculation Method</b>	Minimum Curvature
<b>Well:</b>	Taylor 3-9 C4	<b>Mag Decl.:</b>		<b>Proposed Azimuth</b>	0.00
<b>Location:</b>	Duchesne, UT	<b>Dir Driller:</b>		<b>Depth Reference</b>	KB
<b>Rig:</b>	Precision 406	<b>MWD Eng:</b>		<b>Tie Into:</b>	Gyro/MWD

Survey Number	Survey Depth (ft)	Inclination (deg)	Azimuth (deg)	Course Length (ft)	True Vertical Depth (ft)	Vertical Section (ft)	Coordinates		Closure Distance (ft)	Closure Direction Azimuth	Dogleg Severity (d/100')	Build Rate (d/100')	Walk Rate (d/100')
							N/S (ft)	E/W (ft)					
73	6865.00	0.22	352.35	93.00	6861.15	135.77	135.77 N	0.89 E	135.78	0.37	0.61	-0.19	248.41
74	6958.00	0.70	359.43	93.00	6954.14	136.52	136.52 N	0.86 E	136.52	0.36	0.52	0.52	7.61
75	7052.00	0.09	4.26	94.00	7048.14	137.17	137.17 N	0.86 E	137.17	0.36	0.65	-0.65	-377.84
76	7145.00	0.62	246.53	93.00	7141.14	137.04	137.04 N	0.40 E	137.04	0.17	0.72	0.57	260.51
77	7238.00	1.01	231.77	93.00	7234.13	136.33	136.33 N	0.70 W	136.33	359.70	0.47	0.42	-15.87
78	7332.00	1.41	225.04	94.00	7328.11	135.00	135.00 N	2.17 W	135.02	359.08	0.45	0.43	-7.16
79	7425.00	2.20	217.84	93.00	7421.06	132.78	132.78 N	4.08 W	132.84	358.24	0.88	0.85	-7.74
80	7518.00	2.59	213.53	93.00	7513.98	129.62	129.62 N	6.33 W	129.78	357.20	0.46	0.42	-4.63
81	7611.00	1.80	219.07	93.00	7606.91	126.74	126.74 N	8.41 W	127.01	356.20	0.88	-0.85	5.96
82	7704.00	1.41	220.96	93.00	7699.88	124.74	124.74 N	10.08 W	125.14	355.38	0.42	-0.42	2.03
83	7798.00	1.10	229.04	94.00	7793.85	123.27	123.27 N	11.52 W	123.81	354.66	0.38	-0.33	8.60
84	7891.00	1.19	218.67	93.00	7886.83	121.93	121.93 N	12.80 W	122.60	354.01	0.24	0.10	-11.15
85	7984.00	1.49	187.03	93.00	7979.81	119.98	119.98 N	13.55 W	120.74	353.56	0.84	0.32	-34.02
86	8077.00	1.19	184.66	93.00	8072.79	117.82	117.82 N	13.78 W	118.62	353.33	0.33	-0.32	-2.55
87	8170.00	0.48	131.44	93.00	8165.78	116.60	116.60 N	13.57 W	117.38	353.36	1.05	-0.76	-57.23
88	8264.00	0.62	141.77	94.00	8259.77	115.94	115.94 N	12.96 W	116.66	353.62	0.18	0.15	10.99
89	8357.00	1.58	173.85	93.00	8352.75	114.27	114.27 N	12.51 W	114.95	353.75	1.19	1.03	34.49
90	8450.00	0.48	142.73	93.00	8445.74	112.68	112.68 N	12.13 W	113.33	353.85	1.29	-1.18	-33.46
91	8544.00	0.70	126.34	94.00	8539.73	112.03	112.03 N	11.43 W	112.61	354.17	0.29	0.23	-17.44
92	8638.00	1.01	172.35	94.00	8633.72	110.87	110.87 N	10.86 W	111.40	354.41	0.77	0.33	48.95
93	8731.00	1.01	183.16	93.00	8726.71	109.24	109.24 N	10.80 W	109.77	354.36	0.20	0.00	11.62
94	8824.00	0.88	333.54	93.00	8819.70	109.06	109.06 N	11.16 W	109.63	354.16	1.97	-0.14	161.70
95	8918.00	0.70	280.07	94.00	8913.70	109.80	109.80 N	12.05 W	110.46	353.74	0.78	-0.19	-56.88
96	9010.00	0.70	258.35	92.00	9005.69	109.79	109.79 N	13.15 W	110.57	353.17	0.29	0.00	-23.61
97	9104.00	0.70	287.05	94.00	9099.68	109.84	109.84 N	14.26 W	110.76	352.60	0.37	0.00	30.53
98	9197.00	0.48	224.96	93.00	9192.68	109.73	109.73 N	15.08 W	110.76	352.18	0.69	-0.24	-66.76
99	9217.00	0.09	118.65	20.00	9212.68	109.66	109.66 N	15.13 W	110.70	352.15	2.56	-1.95	-531.55
100	9270.00	0.09	118.65	53.00	9265.68	109.62	109.62 N	15.05 W	110.65	352.18	0.00	0.00	0.00
101	9360.00	1.40	175.28	90.00	9355.67	108.49	108.49 N	14.90 W	109.51	352.18	1.50	1.46	62.93
102	9450.00	1.19	158.81	90.00	9445.65	106.52	106.52 N	14.47 W	107.50	352.26	0.47	-0.23	-18.30
103	9540.00	1.53	178.05	90.00	9535.62	104.45	104.45 N	14.09 W	105.39	352.32	0.62	0.37	21.38
104	9630.00	2.16	175.10	90.00	9625.57	101.56	101.56 N	13.90 W	102.50	352.20	0.71	0.70	-3.28
105	9720.00	1.80	157.08	90.00	9715.52	98.56	98.56 N	13.21 W	99.44	352.37	0.79	-0.40	-20.02
106	9810.00	2.17	188.34	90.00	9805.47	95.57	95.57 N	12.90 W	96.44	352.31	1.25	0.41	34.73
107	9900.00	2.48	187.33	90.00	9895.39	91.95	91.95 N	13.40 W	92.92	351.71	0.35	0.35	-1.12
108	9990.00	2.14	175.31	90.00	9985.32	88.34	88.34 N	13.51 W	89.37	351.30	0.66	-0.38	-13.36
109	10080.00	2.62	193.62	90.00	10075.25	84.66	84.66 N	13.86 W	85.79	350.70	1.00	0.54	20.35

RECEIVED: Dec. 19, 2013



<b>Company:</b>	EP Energy	<b>Job Number:</b>		<b>Calculation Method</b>	Minimum Curvature
<b>Well:</b>	Taylor 3-9 C4	<b>Mag Decl.:</b>		<b>Proposed Azimuth</b>	0.00
<b>Location:</b>	Duchesne, UT	<b>Dir Driller:</b>		<b>Depth Reference</b>	KB
<b>Rig:</b>	Precision 406	<b>MWD Eng:</b>		<b>Tie Into:</b>	Gyro/MWD

Survey Number	Survey Depth (ft)	Inclination (deg)	Azimuth (deg)	Course Length (ft)	True Vertical Depth (ft)	Vertical Section (ft)	Coordinates				Closure		Dogleg Severity (d/100')	Build Rate (d/100')	Walk Rate (d/100')
							N/S (ft)		E/W (ft)		Distance (ft)	Direction Azimuth			
110	10170.00	2.31	179.26	90.00	10165.16	80.84	80.84	N	14.32	W	82.10	349.95	0.77	-0.34	-15.97
111	10260.00	2.42	196.25	90.00	10255.09	77.20	77.20	N	14.83	W	78.61	349.13	0.78	0.11	18.89
112	10350.00	2.06	174.45	90.00	10345.02	73.77	73.77	N	15.20	W	75.32	348.35	1.02	-0.40	-24.22
113	10440.00	2.52	192.66	90.00	10434.95	70.23	70.23	N	15.48	W	71.92	347.57	0.95	0.52	20.23
114	10530.00	1.98	174.95	90.00	10524.88	66.75	66.75	N	15.78	W	68.59	346.70	0.97	-0.60	-19.68
115	10620.00	2.62	192.35	90.00	10614.81	63.19	63.19	N	16.08	W	65.20	345.72	1.04	0.71	19.33
116	10710.00	2.07	180.49	90.00	10704.73	59.55	59.55	N	16.54	W	61.80	344.48	0.81	-0.61	-13.18
117	10800.00	2.68	197.69	90.00	10794.66	55.92	55.92	N	17.19	W	58.51	342.91	1.03	0.68	19.11
118	10890.00	1.87	183.80	90.00	10884.59	52.45	52.45	N	17.93	W	55.43	341.13	1.08	-0.89	-15.44
119	10980.00	2.67	193.15	90.00	10974.51	48.94	48.94	N	18.50	W	52.32	339.29	0.97	0.89	10.40
120	11070.00	2.54	200.27	90.00	11064.42	45.03	45.03	N	19.67	W	49.13	336.40	0.39	-0.14	7.90
121	11160.00	2.67	198.52	90.00	11154.33	41.17	41.17	N	21.03	W	46.23	332.95	0.16	0.14	-1.94
122	11250.00	2.76	187.49	90.00	11244.23	37.04	37.04	N	21.97	W	43.06	329.32	0.59	0.11	-12.25
123	11340.00	3.06	189.69	90.00	11334.11	32.52	32.52	N	22.66	W	39.64	325.13	0.35	0.33	2.44
124	11430.00	2.85	194.71	90.00	11423.99	27.99	27.99	N	23.63	W	36.63	319.83	0.37	-0.23	5.58
125	11520.00	2.36	182.50	90.00	11513.90	23.98	23.98	N	24.28	W	34.13	314.64	0.82	-0.55	-13.57
126	11610.00	2.48	177.27	90.00	11603.82	20.19	20.19	N	24.27	W	31.57	309.75	0.28	0.14	-5.82
127	11700.00	3.19	182.30	90.00	11693.71	15.74	15.74	N	24.28	W	28.93	302.96	0.83	0.78	5.59
128	11790.00	3.51	184.09	90.00	11783.56	10.50	10.50	N	24.57	W	26.72	293.13	0.38	0.36	1.99
129	11880.00	3.41	186.44	90.00	11873.39	5.09	5.09	N	25.07	W	25.58	281.48	0.19	-0.11	2.62
130	11910.00	3.42	181.28	30.00	11903.34	3.31	3.31	N	25.19	W	25.41	277.49	1.03	0.05	-17.21
131	12000.00	3.42	181.28	90.00	11993.18	-2.06	2.06	S	25.31	W	25.39	265.34	0.00	0.00	0.00

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> Fee
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> EP ENERGY E&P COMPANY, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1001 Louisiana, Houston, TX, 77002		<b>8. WELL NAME and NUMBER:</b> Taylor 3-9C4
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0900 FSL 1750 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWSE Section: 09 Township: 03.0S Range: 04.0W Meridian: U		<b>9. API NUMBER:</b> 43013519540000
<b>PHONE NUMBER:</b> 713 997-5038 Ext		<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: <b>12/3/2015</b>	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
 EP plans to recomplete well from the Wasatch to the LGR. See attached for further details.

Approved by the  
 December 01, 2015  
 Oil, Gas and Mining

Date: \_\_\_\_\_

By: Derek Duff

<b>NAME (PLEASE PRINT)</b> Maria S. Gomez	<b>PHONE NUMBER</b> 713 997-5038	<b>TITLE</b> Principal Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 12/1/2015	

## *Taylor 3-9C4 Recom Summary Procedure*

- POOH with rods, pump & tubing. Inspect/Repair/Re-furbish as needed. Replace any bad tubing and joints of rods.
- Set two CBPs for 5" 18# casing @ 9,300' & 9,280' to plug back currently producing zones (Top perf @ 9,311'). Dump bail 50' sand on top of plug @ 9,280'.
- Stage 1:
  - Perforate new LGR interval from **9,027 – 9,211'**.
  - Prop Frac Perforations with **92,000** lbs 30/50 prop (w/ **3,000** lbs 100 mesh & **5,000** gals 15% HCl acid) (Stage 1 Recom).
- Stage 2:
  - RIH with 7" CBP & set @ 8,944'.
  - Perforate new LGR interval from **8,857 – 8,929'**.
  - Prop Frac Perforations with **40,000** lbs 30/50 prop (w/ **3,000** lbs 100 mesh & **5,000** gals 15% HCl acid) (Stage 2 Recom).
- Stage 3:
  - RIH w/ 7" CBP & set @ 8,578'.
  - Perforate new LGR interval from **8,390 – 8,563'**.
  - Prop frac perforations with **90,000** lbs 30/50 prop (w/ **3,000** lbs 100 mesh & **5,000** gals 15% HCl acid) (Stage 3 Recom).
- Clean out well drilling up (2) 7" CBP's, leaving 30' sand on top of 5" CBP @ 9,280'. Top perf BELOW plug @ 9,311'.
- RIH w/ production tubing and rods.
- Clean location and resume production.



# Current Pumping Schematic

Company Name: EP EnergyWell Name: Taylor 3-9C4Field, County, State: Altamont - Bluebell, Duchesne, UtahSurface Location: Lat: 40° 13' 48.87713" N Long: 110° 20' 17.45761" WProducing Zone(s): WasatchLast Updated: November 5, 2015By: TomovaTD: 12,000'

NHOW: \_\_\_\_\_

PICK UP: \_\_\_\_\_

263 Jts 2-7/8" 6.5# N-80 8rd Tubing

9-5/8" 40# N-80 LTC @ 3,640' MD

Poor cmt 3390'-6234'

TOC @ 6234'

Rod Detail @ 4.3 SPM  
1-1/2" x 40' Polished Rod  
1,036' - 18/16" CoRod  
1,066' - 17/16" CoRod  
1,251' - 16/16" CoRod  
6,191' - 15/16" CoRod  
1,360' - 16/16" CoRod  
2" x 1-1/2" x 38' Insert Pump

2-7/8" x 2-3/8" Crossover @ 8,921'  
~61 jts of 2-3/8" 4.7# N-80 8rd Tubing  
TOL @ 8,994'

7" 29# HCP-110 LTC @ 9,271'  
 Drift I.D. - 6.059"

## Initial Completion Perfs - Apr '13

9,311' - 9,592' (23'/69 holes)  
5,000 Gals 15% HCL + 140,000# 20/40  
 9,622' - 9,864' (23'/69 holes)  
5,000 Gals 15% HCL + 140,000# 20/40  
 9,896' - 10,109' (22'/66 holes)  
5,000 Gals 15% HCL + 140,000# 20/40  
 10,139' - 10,394' (23'/69 holes)  
5,000 Gals 15% HCL + 155,000# 20/40  
 10,418' - 10,736' (23'/69 holes)  
5,000 Gals 15% HCL + 155,000# 20/40  
 10,760' - 11,043' (23'/69 holes)  
5,000 Gals 15% HCL + 155,000# 20/40  
 11,074' - 11,444' (20'/60 holes)  
5,000 Gals 15% HCL + 115,000# 20/40  
 11,494' - 11,858' (23'/69 holes)  
5,000 Gals 15% HCL + 140,000# 20/40

Tubing Anchor @ 10,882'  
4 jts 2-3/8" 4.7# N-80 8rd Tubing  
Seating Nipple @ ~11,014'  
2' x 2 3/8" Tubing Sub  
De-sander - D2303  
2 jt 2-3/8" Mud Anchor  
EOT @ ~11,103'

5" 18# P-110 STL @ 11,997'  
 Drift ID 4.151"



### Proposed Recom Pumping Schematic

Company Name: EP EnergyWell Name: Taylor 3-9C4Field, County, State: Altamont - Bluebell, Duchesne, UtahSurface Location: Lat: 40° 13' 48.87713" N Long: 110° 20' 17.45761" WProducing Zone(s): WasatchLast Updated: November 25, 2015By: KrugTD: 12,000'

NHOW: \_\_\_\_\_

PICK UP: \_\_\_\_\_

#### 253 Jts 2-7/8" 6.5# N-80 8rd Tubing

**Rod Detail @ 4.3 SPM**  
**1-1/2" x 40' Polished Rod**  
**1,065' - 18/16" CoRod**  
**1,088' - 17/16" CoRod**  
**1,251' - 16/16" CoRod**  
**3,486' - 15/16" CoRod**  
**1,360' - 16/16" CoRod**

9-5/8" 40# N-80 LTC @ 3,640' MD

Poor cmt 3390'-6234'

TOC @ 6234'

**Tubing Anchor @ 8,125'**  
**4 jts 2-7/8" 6.5# L-80 8rd Tubing**  
**Seating Nipple @ 8,250'**  
**2' x 2 7/8" Tubing Sub**  
**5 1/2" x 30' PBGA**  
**2 jts 2-7/8" Mud Anchor**  
**5 3/4" No-Go Nipple**  
**EOT @ 8,350'**

TOL @ 8,994'

7" 29# HCP-110 LTC @ 9,271'

Drift I.D. - 6.059"

CBP @ 9,280' w/ 50' sand

CBP @ 9,300'

#### Initial Completion Perfs - Apr '13

9,311' - 9,592' (23'/69 holes)  
**5,000 Gals 15% HCL + 140,000# 20/40**  
 9,622' - 9,864' (23'/69 holes)  
**5,000 Gals 15% HCL + 140,000# 20/40**  
 9,896' - 10,109' (22'/66 holes)  
**5,000 Gals 15% HCL + 140,000# 20/40**  
 10,139' - 10,394' (23'/69 holes)  
**5,000 Gals 15% HCL + 155,000# 20/40**  
 10,418' - 10,736' (23'/69 holes)  
**5,000 Gals 15% HCL + 155,000# 20/40**  
 10,760' - 11,043' (23'/69 holes)  
**5,000 Gals 15% HCL + 155,000# 20/40**  
 11,074' - 11,444' (20'/60 holes)  
**5,000 Gals 15% HCL + 115,000# 20/40**  
 11,494' - 11,858' (23'/69 holes)  
**5,000 Gals 15% HCL + 140,000# 20/40**

5" 18# P-110 STL @ 11,997'  
 Drift ID 4.151"



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

RECOMPLETION

AMENDED REPORT ☐ FORM 8  
(highlight changes)

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME

8. WELL NAME and NUMBER:

9. API NUMBER:

10 FIELD AND POOL, OR WILDCAT

11. QTR/QTR, SECTION, TOWNSHIP, RANGE,  
MERIDIAN:

12. COUNTY

13. STATE

UTAH

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☐ DRY ☐ OTHER \_\_\_\_\_b. TYPE OF WORK: NEW WELL ☐ HORIZ. LATS. ☐ DEEP-EN ☐ RE-ENTRY ☐ DIFF. RESVR. ☐ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:

3. ADDRESS OF OPERATOR:

CITY

STATE

ZIP

PHONE NUMBER:

4. LOCATION OF WELL (FOOTAGES)

AT SURFACE:

AT TOP PRODUCING INTERVAL REPORTED BELOW:

AT TOTAL DEPTH:

14. DATE SPUDDED:

15. DATE T.D. REACHED:

16. DATE COMPLETED:

ABANDONED ☐READY TO PRODUCE ☐

17. ELEVATIONS (DF, RKB, RT, GL):

18. TOTAL DEPTH: MD

TVD

19. PLUG BACK T.D.: MD

TVD

20. IF MULTIPLE COMPLETIONS, HOW MANY? \*

21. DEPTH BRIDGE MD

PLUG SET: TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

23.

WAS WELL CORED?

NO ☐YES ☐

(Submit analysis)

WAS DST RUN?

NO ☐YES ☐

(Submit report)

DIRECTIONAL SURVEY?

NO ☐YES ☐

(Submit copy)

## 24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED

## 25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)

## 26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)
(A)				
(B)				
(C)				
(D)				

## 27. PERFORATION RECORD

INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

## 28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC. See attached for further information on #27 &amp; #28.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL

29. ENCLOSED ATTACHMENTS: Plugs @ 9300', 9290' &amp; 9275' w/50' on top (9225')

30. WELL STATUS:

☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY  
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: \_\_\_\_\_

**31. INITIAL PRODUCTION****INTERVAL A (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL B (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL C (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**INTERVAL D (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

**32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)****33. SUMMARY OF POROUS ZONES (Include Aquifers):**

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

**34. FORMATION (Log) MARKERS:**

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)

**35. ADDITIONAL REMARKS (Include plugging procedure)**

**36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.**

NAME (PLEASE PRINT) \_\_\_\_\_ TITLE \_\_\_\_\_

SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

## 1 General

### 1.1 Customer Information

Company	CENTRAL DIVISION
Representative	
Address	

### 1.2 Well Information

Well	TAYLOR 3-9C4		
Project	ALTAMONT FIELD	Site	TAYLOR 3-9C4
Rig Name/No.		Event	RECOMPLETE LAND
Start date	12/2/2015	End date	12/14/2015
Spud Date/Time	3/18/2013	UWI	TAYLOR 3-9C4
Active datum	KB @6,016.1ft (above Mean Sea Level)		
Afe No./Description	165925/55384 / TAYLOR 3-9C4		

## 2 Summary

### 2.1 Operation Summary

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
12/3/2015	14:00 16:00	2.00	UNINARTLT	03		P		PUMP 70 BBLs DWN CSG W/ HOT OILER, SLIDE P.U. BACK, SPOT IN & RU COROD RIG, LD POLISH ROD, WORK PUMP OFF SEAT
	16:00 17:30	1.50	UNINARTLT	03		P		SPOOL OUT OF HOLE W/ 6000' COROD, SECURE WELL SDFN
12/4/2015	6:00 7:30	1.50	UNINARTLT	28		P		CT HOLD SAFETY MTG ON SLIPS & FALLS, WRITE & REVIEW JSA'S
	7:30 10:00	2.50	UNINARTLT	03		P		OPEN WELL, CONT TOO H W/ 5000' COROD, LD PUMP, RIG DWN & MOVE OFF LOC W/ COROD RIG
	10:00 12:00	2.00	WOR	16		P		SPOT IN & RU PEAK 1500, NDWH, PU BREAK OUT & LD, 10K B FLANGE, MU 6' 2-7/8" TBG SUB & TBG HANGER, TEMP LAND TBG ON HANGER, NU 5K BOP & TEST TO 4800 PSI W/ HOT OILER GOOD TEST, RU WORK FLOOR & TBG TONGS
	12:00 15:00	3.00	WOR	39		P		RELEASE 5" TAC, RU TBG SCANNERS SCAN OUT OF HOLE W/ 273 JTS 2-7/8" EUE L-80 TBG, 256 JTS YELLOW BAND, 16 JTS BLUE BAND & 1 JT RED BAND, RIG DWN TBG SCANNING EQUIP
	15:00 16:30	1.50	WOR	24		P		POOH & LD 2-7/8" X 2-3/8" EUE X OVER, 61 JTS 2-3/8" EUE N-80 TBG, 5" TAC, 4 JTS 2-3/8" TBG, P.S.N., 1 JT 2-3/8", 2-3/8" DESANDER, 2 JTS 2-3/8" TBG & 2-3/8" SOLID BULL PLUG, SECURE WELL, CLOSE & LOCK BLIND RAMS, CLOSE CSG VALVES & NIGHT CAP, SDFN
12/5/2015	6:00 7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON WIRE LINE OPERATIONS, WRITE & REVIEW JSA'S
	7:30 17:30	10.00	WLWORK	26		P		MIRI WIRE LINE, RIH W/ 5" GR/JB TO 9310', & 7" GR/JB TO 5" LT, RIH & SET 5" COMPOSITE CBP @ 9300', FILL CSG W/ 340 BBLs TREATED 2% KCL ATTEMPT TO PRESSURE TEST CSG, PRESSURE UP CSG TO 2200 PSI & BLEED OF TO 0 PSI IN 3 MIN, SET 2ND CBP @ 9290' TEST CSG TO 2200 PSI GOOD TEST, RIH w/ 3RD 5" CBP, PRESSURE UP CSG TO 2200 PSI & SET 5" CBP @ 9275' BLEED OFF PRESSURE, RIH & DUMP BAIL 50' SAND ONTOP OF 3RD CBP @ 9275' TOP OF SAND @ 9225', POOH & RD WIRE LINE
	17:30 19:00	1.50	WOR	16		P		RD WORK FLOOR, NDBOP NU 7" FRAC VALVE, TEST CSG TO 8000 PSI FOR 15 MIN GOOD TEST, NU NIGHT CAP ON FRAC VALVE, CLOSE FRAC VALVE, CSG VALVES & NIGHT CAP SDFN

## 2.1 Operation Summary (Continued)

Date	Time Start-End		Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
12/6/2015	6:00	6:00	24.00	WOR	18		P		NO ACTIVITY SDFW
12/7/2015	6:00	6:00	24.00	WOR	18		P		NO ACTIVITY SDFW
12/8/2015	6:00	7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON USING TAG LINES & STAYING OUT OF LINE OF FIRE, WRITE & REVIEW JSA'S
	7:30	9:30	2.00	WOR	16		P		ND 10K NIGHT CAP, NU 7" HCR VALVES & GOAT HEAD, TEST TO 9500 PSI GOOD TEST
	9:30	12:00	2.50	STG01	21		P		SPOT IN & RIG UP WIRE LINE, TEST LUBRICATOR to 4500 PSI W/ HOT OILER, RIH & SHOOT STG 1 PERFS FROM 9186' TO 9027' USING 2-3/4" TAG - RTG GUNS, 16 GM CHARGES @ 120 DEG PHASING, ALL PERFS CORRELATED TO LONE WOLF CBL/CCL LOG DATED 4/21/2013, STARTING PRESSURE 1000 PSI, ENDING PRESSURE 250 PSI, POOH LD GUNS & SWI, CLOSE MASTER FRAC VALVE, BOTH HCR VALVES & NIGHT CAP TOP OF STACK, CLOSE & NIGHT CAP CSG VALVES
	12:00	17:00	5.00	MIRU	01		P		MOVE IN & RU HALLIBURTON FRAC EQUIP, RUN FLOW BACK LINES, WATER TRANSFER LINES & HEAT FRAC WTR, SDFN
12/9/2015	6:00	7:30	1.50	STG01	28		P		CT HOLD AFETY MTG ON FRACING OPERATIONS, WRITE & REVIEW JSA'S
	7:30	9:30	2.00	STG01	18		P		CONT RU HALLIBURTON FRAC EQUIP, START & WARM UP EQUIP
	9:30	11:00	1.50	STG01	35		P		PRESSURE TEST PUMP LINES TO 9215 PSI. OPEN WELL. SICP 15 PSI. FILL CSG W/ 100 BBLS, BREAK DOWN STAGE 1 PERFORATIONS @ 3667 PSI, PUMPING 10 BPM. BRING RATE UPTO 40 BPM. PUMP 224 TTL BBLS FLUID THEN PERFORM STEP RATE SHUT DOWN TEST. ISIP 2871 PSI. FG .72. 5 MIN 2595 PSI. 10 MIN 2445 PSI. TREAT STAGE 1 PERFORATIONS W/ 5,000 GALLONS 15% HCL ACID, 3000 LBS 100 MESH SAND IN 1/2 PPG STAGE & 90,000 LBS WHITE 30/50 SAND IN 1/2 PPG, 1 PPG, 1.75 PPG & 2.5 PPG STAGES. ISIP 2964 PSI. FG .73. AVG RATE 70 BPM. MAX RATE 73.7 BPM. AVG PSI 5375 PSI. MAX PSI 7329 PSI. SHUT IN WELL & TURN OVER TO WIRE LINE, 3195 BBLS FLUID TO RECOVER.
	11:00	13:30	2.50	STG02	21		P		RIH & SET 7" CBP @ 8925'. PERFORATE STAGE 2 PERFORATIONS FROM 8902' TO 8857', USING 3-1/8" TAG-RTG GUNS, 22.7 GRAM CHARGES, 3 SPF, 120 DEGREE PHASING. ALL PERFS CORRELATED TO LONE WOLF CBL/GR/CCL RUN 1 LOG DATED 04/21/2013, STARTING PRESSURE 2400 PSI, ENDING 2200 PSI, POOH W/ W.L., SHUT WELL IN & TURN OVER TO FRAC CREW
	13:30	15:00	1.50	STG02	35		P		PRESSURE TEST PUMP LINES TO 9044 PSI. OPEN WELL. SICP 2125 PSI. BREAK DOWN STAGE 2 PERFORATIONS @ 3294 PSI, PUMPING 10 BPM. BRING RATE UPTO 40 BPM. PUMP 83 TTL BBLS FLUID THEN PERFORM STEP RATE SHUT DOWN TEST. ISIP 2627 PSI. FG .73. 5 MIN 2000 PSI. 10 MIN 1918 PSI. TREAT STAGE 2 PERFORATIONS W/ 5,000 GALLONS 15% HCL ACID, 3000 LBS 100 MESH SAND IN 1/2 PPG STAGE & 24,200 LBS WHITE 30/50 SAND IN 1/2 PPG & 1 PPG EXTENDED 1 PPG STG SCREENED OUT ON 1 PPG STG 11,400#S IN PERFS & 12,800#S IN WELL BORE. ISIP 7985 PSI. AVG RATE 43.5 BPM. MAX RATE 62.2 BPM. AVG PSI 7302 PSI. MAX PSI 7985 PSI. SHUT IN WELL.
	15:00	16:00	1.00	STG02	18		N		FLUSH OUT PUMPS & PUMP LINES TO FLOW BACK TANKS
	16:00	6:00	14.00	STG02	19		N		OPEN CSG TO FLOW BACK TANKS @ 300 PSI ON 64/64 CHOKE, FLOWED BACK 171 TOTAL BBLS WATER @ 04:00
12/10/2015	6:00	7:30	1.50	STG02	28		N		CT HOLD SAFETY MTG ON WIRE LINE OPERATIONS WRITE & REVIEW JSA'S
	7:30	9:00	1.50	WLWORK	18		N		0 PSI ON WELL. RIH W/ 2-3/4" SINKER BARS TAG 7" CBP @ 8925', POOH W/ W.L. SWI & TURN WELL OVER TO FRAC

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
	9:00 11:00	2.00	STG02	18		N		TEST PUMP LINES TO 8990 PSI, OPEN WELL 0 PSI, ATTEMPT TO FLUSH 7" CSG PUMPED 8 BBLS WATER & PRESSURED UP TO 8000 PSI, SWI & FLUSH PUMPS & PUMP LINES W/ BRINE WTR
	11:00 13:00	2.00	WOR	16		N		RD WIRE LINE, & FRAC LINES FROM STACK, ND GOAT HEAD & TOP HCR VALVE, NU & TEST 5K BOP TO 4800 PSI GOOD TEST, RU WORK FLOOR & TBG TONGS
	13:00 16:00	3.00	WOR	39		N		MU & RIH W/ 6" ROCK BIT, BIT SUB, TALLY & RIN IN HOLE W/ 273 JTS 2-7/8" EUE L-80 TBG, EOT @ 8906' (BTM PERF @ 8902')
	16:00 17:15	1.25	WOR	06		N		CIRC WELL BORE W/ 350 BBLS TREATED 2% KCL
	17:15 19:30	2.25	WOR	39		N		TOOH W/ 273 JTS 2-7/8" EUE L-80 TBG, CLOSE 7" FRAC VALVE, 7" HCR VALVE & LOCK IT, CLOSE & NIGHT CAP CSG VALVES SDFN
12/11/2015	6:00 7:30	1.50	STG03	28		N		CT HOLD SAFETY MTG ON NDBOP & NUFRAC STACK WRITE & REVIEW JSA'S
	7:30 9:30	2.00	WOR	16		N		RD TBG TONGS & WORK FLOOR, ND5K BOP, NU 7" HCR, GOAT HEAD & TEST FRAC STACK TO 9500 PSI GOOD TEST
	9:30 12:30	3.00	STG03	21		P		RU WIRE LINE RIH W/ 6" OD GR/JB TO 8590', POOH, RIH W/ 7" CBP & PERF GUNS, SET 7" CBP @ 8578', PERF STG 3 PERFS 8563'-8390' USING 3-1/8" TAG RTG GUNS, 22.7 GM CHARGES @ 120 DEG PHASING, ALL PERFS CORRELATED TO THE LONE WOLF CBL/GR/CCL LOG DATED 4/21/2013, STARTING PRESSURE 900 PSI, ENDING PRESSURE 800 PSI, POOH SWI & TURN OVER TO FRAC CREW
	12:30 15:00	2.50	STG03	35		P		RU FRAC LINES TO FRAC STACK, PRESSURE TEST PUMP LINES TO 8994 PSI. OPEN WELL. SICP 389 PSI. BREAK DOWN STAGE 3 PERFORATIONS @ 2872 PSI, PUMPING 5.5 BPM. BRING RATE UPTO 40 BPM. PUMP 94 TTL BBLS FLUID THEN PERFORM STEP RATE SHUT DOWN TEST. ISIP 1790 PSI. FG .65. 5 MIN 1340 PSI. 10 MIN 1131 PSI. TREAT STAGE 3 PERFORATIONS W/ 5,000 GALLONS 15% HCL ACID, 3000 LBS 100 MESH SAND IN 1/2 PPG STAGE & 98,480 LBS WHITE 30/50 SAND IN 1/2 PPG, 1 PPG, 1.75 PPG & 2.25 PPG STAGES. ISIP 1884 PSI. FG .66. AVG RATE 74 BPM. MAX RATE 76.5 BPM. AVG PSI 2865 PSI. MAX PSI 4356 PSI. SHUT IN WELL. 3281 BBLS FLUID TO RECOVER.
	15:00 18:00	3.00	RDMO	02		P		RIG DWN & MOVE OUT FRAC & WIRE LINE EQUIPMENT
	18:00 6:00	12.00	FB	19		P		OPEN WELL TO FLOW BACK TANKS ON 12/64 CHOKE @ 1050 PSI, FLOWED 504 BBLS WATER, CURRENT PRESSURE 825 , CURRENT CHOKE 12/64
12/12/2015	6:00 7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON ND FRAC STACK WRITE & REVIEW JSA'S
	7:30 10:00	2.50	WOR	16		P		ND GOAT HEAD & TOP HCR VALVE, NU NIGHT CAP ON BTM HCR VALVE, WHILE FLOW TESTING WELL
	10:00 6:00	20.00	FB	19		P		STG 3 PERFS FLOWING BACK, CURRENT PRESSURE 850 PSI, ON 12/64 CHOKE FLOWED BACK 826 BBLS WATER
12/13/2015	6:00 6:00	24.00	FB	19		P		HOLD SAFETY MTG ON TURNING WELL TO PROD FACILITY WRITE & REVIEW JSA'S, CURRENT PSI 850 PSI FLOWED BACK 826 BLS H2O TO FLOW BACK TANK
12/14/2015	6:00 6:00	24.00	FB	19		P		HOLD SAFETY MTG ON CHANGING GAUGES, WRITE & REVIEW JSA'S, CURRENT PRESSURE 750 PSI, FLOWED 667 BBLS OIL, 321 BBLS WATER ON 18/64 CHOKE
12/15/2015	6:00 7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON RU WIRE LINE LUBRICATOR WRITE & REVIEW JSA'S
	7:30 10:30	3.00	WLWORK	20		P		MIRU WIRE LINE, RIH W/ 7" ARROW SET PKR W/ PUMP OUT PLUG & PLUG CATCHER, SET PKR @ 8150', POOH RD WIRE LINE

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity	Sub	OP Code	MD from (ft)	Operation
	10:30 12:30	2.00	WOR	19		P		BLOW WELL DWN RECOVERING 192 BBLS OIL & 85 BBLS WATER
	12:30 14:00	1.50	WOR	16		P		ND 7" HCR VALVE, NU & TEST 5K BOP, RU WORK FLOOR & TBG TONGS
	14:00 15:30	1.50	WOR	39		P		MU & RIH W/ 7" ON-OFF SKIRT & 251 JTS 2-7/8" TBG, LATCH ONTO PKR & SPACE OUT, J-OFF PKR, LD 2 JT 2-7/8" TBG
	15:30 16:30	1.00	WOR	06		P		CIRC WELL BORE W/ 300 BBLS 2% KCL & PKR FLUID
	16:30 18:30	2.00	WOR	16		P		RIH W/ 1 JT 2-7/8" TBG, WEATHERFORD BREECH LOCK TBG HANGER W/ TWO WAY VALVE, LAND TBG HANGER & LOCK IN BOWL J-OUT OF HANGER RIH & LATCH ONTO PKR, PULL UP & LAND HANGER IN BOWL IN 12K TENSION, RD TBG TONGS & WORK FLOOR, NDBOP, & 10K FRAC VALVE, NU & TEST FLOW TREE & FLOW LINES, PUMP OUT PLUG IN PKR @ 2100 PSI, TBG WENT ON VACUME
	18:30 6:00	11.50	FB	19		P		TURN WELL OVER TO FLOW BACK CREW, OPEN WELL TO FLOW BACK TANK 0 PSI, @ 21:30 WELL HAD 375 PSI & TURN TO PROD FACILITY, CURRENT PRESSURE 825 PSI ON 18/64 CHOKE, FLOWED 363 BBLS OIL & 226 BBLS WATER
12/31/2015	11:00 19:00	8.00	SL	18		P		RU SLICK LINE UNIT & HOT OIL UNITS. PRESSURE TEST ANNULUS TO 100 PSI FOR 15 MINUTES. TESTED GOOD. RIH W/ 1-1/2" SINKER BARS. TAG OBSTRUCTION @ TBG HANGER AREA, 8' FROM TOP OF WELLHEAD. ATTEMPTS TO WORK DEEPER FAILED. PUMP5 BBLS 200 DEGREE 2% KCLWTR DOWN TBG @ 800 PSI. RIH W/ 2-1/4" OD IMPRESSION BLOCK.. TAG OBSTRUCTION & WORK SPANG JARS. POOH. DID NOT MARK FACE OF IMPRESSION BLOCK. SIDES OF IMPRESSION BLOCK SHOWED MARKING AS IF OBSTRUCTION TAPERED TO CENTER OF TBG. RIH W/ 1-3/4" IMPRESSION BLOCK. W/ IMPRESSION BLOCK SHOW NO MARK ON FACE & MARKING TAPERED TO CENTER OF TBG ON OUT SIDE EDGE OF BLOCK. RIH W/ WIRE TBG SCRATCHER FOR 2-7/8" TBG. TAG OBSTRUCTION . ATTEMPTS TOWORK THROUGH OBSTRUCTION FAILED. POOH. SCRATCHER HUNG UP 2' FROM TOP OF WELL HEAD. WORK FREE & POOH. COULD SEE NO DAMAGE TO SCRATCHER. RIH W/ 1-1/2" SINKER BARS TO 6000', FIGHTING HEAVY PARRIFEN TO 400'. POOH. RIH W/ 2"OD PARRIFEN KNIFE TO 6000' W/ HEAVY PARRIFEN TO 400'. POOH. WORK / 2-1/2" PARRIFEN KNIFE TO 90'. UNABLE TO WORK DEEPER. POOH. WORK 2-1/4" PARRIFEN KNIFE TO 136' UNABLE TO WORK DEEPER. POOH & SDFN

Table of Contents

1	General.....	1
1.1	Customer Information.....	1
1.2	Well Information.....	1
2	Summary.....	1
2.1	Operation Summary.....	1



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> Fee
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> EP ENERGY E&P COMPANY, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1001 Louisiana, Houston, TX, 77002		<b>8. WELL NAME and NUMBER:</b> Taylor 3-9C4
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0900 FSL 1750 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWSE Section: 09 Township: 03.0S Range: 04.0W Meridian: U		<b>9. API NUMBER:</b> 43013519540000
<b>PHONE NUMBER:</b> 713 997-5038 Ext		<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: <b>2/29/2016</b>	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text" value="DO Plugs"/>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  

EP plans to drill out plugs @ 8578' & 8917'.

Approved by the

Feb 25, 2016

Oil, Gas and Mining

Date: \_\_\_\_\_

By: Derek Duff

<b>NAME (PLEASE PRINT)</b> Maria S. Gomez	<b>PHONE NUMBER</b> 713 997-5038	<b>TITLE</b> Principal Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 2/25/2016	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> Fee
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> EP ENERGY E&P COMPANY, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1001 Louisiana, Houston, TX, 77002		<b>8. WELL NAME and NUMBER:</b> Taylor 3-9C4
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0900 FSL 1750 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWSE Section: 09 Township: 03.0S Range: 04.0W Meridian: U		<b>9. API NUMBER:</b> 43013519540000
<b>PHONE NUMBER:</b> 713 997-5138 Ext		<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION  OTHER: <input style="width: 100px;" type="text" value="Drill Out 2 Plugs"/>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <b>3/7/2016</b>			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
 Drill out CBP's @ 8578' and 8925'. Return well to production. See attached daily operations report for details (this work starts on page 4).

Accepted by the  
 Utah Division of  
 Oil, Gas and Mining  
**FOR RECORD ONLY**  
 July 21, 2016

<b>NAME (PLEASE PRINT)</b> Linda Renken	<b>PHONE NUMBER</b> 713 997-5138	<b>TITLE</b> Sr. Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 7/18/2016	

## CENTRAL DIVISION

ALTAMONT FIELD

TAYLOR 3-9C4

TAYLOR 3-9C4

RECOMPLETE LAND

### Operation Summary Report

Disclaimer: Although the information contained in this report is based on sound engineering practices, the copyright owner(s) does (do) not accept any responsibility whatsoever, in negligence or otherwise, for any loss or damage arising from the possession or use of the report whether in terms of correctness or otherwise. The application, therefore, by the user of this report or any part thereof, is solely at the user's own risk.

## 1 General

### 1.1 Customer Information

Company	CENTRAL DIVISION
Representative	
Address	

### 1.2 Well Information

Well	TAYLOR 3-9C4		
Project	ALTAMONT FIELD	Site	TAYLOR 3-9C4
Rig Name/No.		Event	RECOMPLETE LAND
Start date	12/2/2015	End date	12/14/2015
Spud Date/Time	3/18/2013	UWI	TAYLOR 3-9C4
Active datum	KB @6,016.1usft (above Mean Sea Level)		
Afe No./Description	165925/55384 / TAYLOR 3-9C4		

## 2 Summary

### 2.1 Operation Summary

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
12/3/2015	14:00 16:00	2.00	UNINARTL T	03		P		PUMP 70 BBLS DWN CSG W/ HOT OILER, SLIDE P.U. BACK, SPOT IN & RU COROD RIG, LD POLISH ROD, WORK PUMP OFF SEAT
	16:00 17:30	1.50	UNINARTL T	03		P		SPOOL OUT OF HOLE W/ 6000' COROD, SECURE WELL SDFN
12/4/2015	6:00 7:30	1.50	UNINARTL T	28		P		CT HOLD SAFETY MTG ON SLIPS & FALLS, WRITE & REVIEW JSA'S
	7:30 10:00	2.50	UNINARTL T	03		P		OPEN WELL, CONT TOO H W/ 5000' COROD, LD PUMP, RIG DWN & MOVE OFF LOC W/ COROD RIG
	10:00 12:00	2.00	WOR	16		P		SPOT IN & RU PEAK 1500, NDWH, PU BREAK OUT & LD, 10K B FLANGE, MU 6' 2-7/8" TBG SUB & TBG HANGER, TEMP LAND TBG ON HANGER, NU 5K BOP & TEST TO 4800 PSI W/ HOT OILER GOOD TEST, RU WORK FLOOR & TBG TONGS
	12:00 15:00	3.00	WOR	39		P		RELEASE 5" TAC, RU TBG SCANNERS SCAN OUT OF HOLE W/ 273 JTS 2-7/8" EUE L-80 TBG, 256 JTS YELLOW BAND, 16 JTS BLUE BAND & 1 JT RED BAND, RIG DWN TBG SCANNING EQUIP
	15:00 16:30	1.50	WOR	24		P		POOH & LD 2-7/8" X 2-3/8" EUE X OVER, 61 JTS 2-3/8" EUE N-80 TBG, 5" TAC, 4 JTS 2-3/8" TBG, P.S.N., 1 JT 2-3/8", 2-3/8" DESANDER, 2 JTS 2-3/8" TBG & 2-3/8" SOLID BULL PLUG, SECURE WELL, CLOSE & LOCK BLIND RAMS, CLOSE CSG VALVES & NIGHT CAP, SDFN
12/5/2015	6:00 7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON WIRE LINE OPERATIONS, WRITE & REVIEW JSA'S
	7:30 17:30	10.00	WLWORK	26		P		MIRI WIRE LINE, RIH W/ 5" GR/JB TO 9310', & 7" GR/JB TO 5' LT, RIH & SET 5" COMPOSITE CBP @ 9300', FILL CSG W/ 340 BBLS TREATED 2% KCL ATTEMPT TO PRESSURE TEST CSG, PRESSURE UP CSG TO 2200 PSI & BLEED OFF TO 0 PSI IN 3 MIN, SET 2ND CBP @ 9290' TEST CSG TO 2200 PSI GOOD TEST, RIH w/ 3RD 5" CBP, PRESSURE UP CSG TO 2200 PSI & SET 5" CBP @ 9275' BLEED OFF PRESSURE, RIH & DUMP BAIL 50' SAND ONTOP OF 3RD CBP @ 9275' TOP OF SAND @ 9225', POOH & RD WIRE LINE
	17:30 19:00	1.50	WOR	16		P		RD WORK FLOOR, NDBOP NU 7" FRAC VALVE, TEST CSG TO 8000 PSI FOR 15 MIN GOOD TEST, NU NIGHT CAP ON FRAC VALVE, CLOSE FRAC VALVE, CSG VALVES & NIGHT CAP SDFN
12/6/2015	6:00 6:00	24.00	WOR	18		P		NO ACTIVITY SDFW

## 2.1 Operation Summary (Continued)

Date	Time Start-End		Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
12/7/2015	6:00	6:00	24.00	WOR	18		P		NO ACTIVITY SDFW
12/8/2015	6:00	7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON USING TAG LINES & STAYING OUT OF LINE OF FIRE, WRITE & REVIEW JSA'S
	7:30	9:30	2.00	WOR	16		P		ND 10K NIGHT CAP, NU 7" HCR VALVES & GOAT HEAD, TEST TO 9500 PSI GOOD TEST
	9:30	12:00	2.50	STG01	21		P		SPOT IN & RIG UP WIRE LINE, TEST LUBRICATOR to 4500 PSI W/ HOT OILER, RIH & SHOOT STG 1 PERFS FROM 9186' TO 9027' USING 2-3/4" TAG - RTG GUNS, 16 GM CHARGES @ 120 DEG PHASING, ALL PERFS CORRELATED TO LONE WOLF CBL/CCL LOG DATED 4/21/2013, STARTING PRESSURE 1000 PSI, ENDING PRESSURE 250 PSI, POOH LD GUNS & SWI, CLOSE MASTER FRAC VALVE, BOTH HCR VALVES & NIGHT CAP TOP OF STACK, CLOSE & NIGHT CAP CSG VALVES
	12:00	17:00	5.00	MIRU	01		P		MOVE IN & RU HALLIBURTON FRAC EQUIP, RUN FLOW BACK LINES, WATER TRANSFER LINES & HEAT FRAC WTR, SDFN
12/9/2015	6:00	7:30	1.50	STG01	28		P		CT HOLD AFETY MTG ON FRACING OPERATIONS, WRITE & REVIEW JSA'S
	7:30	9:30	2.00	STG01	18		P		CONT RU HALLIBURTON FRAC EQUIP, START & WARM UP EQUIP
	9:30	11:00	1.50	STG01	35		P		PRESSURE TEST PUMP LINES TO 9215 PSI. OPEN WELL. SICP 15 PSI. FILL CSG W/ 100 BBLS, BREAK DOWN STAGE 1 PERFORATIONS @ 3667 PSI, PUMPING 10 BPM. BRING RATE UPTO 40 BPM. PUMP 224 TTL BBLS FLUID THEN PERFORM STEP RATE SHUT DOWN TEST. ISIP 2871 PSI. FG .72. 5 MIN 2595 PSI. 10 MIN 2445 PSI. TREAT STAGE 1 PERFORATIONS W/ 5,000 GALLONS 15% HCL ACID, 3000 LBS 100 MESH SAND IN 1/2 PPG STAGE & 90,000 LBS WHITE 30/50 SAND IN 1/2 PPG, 1 PPG, 1.75 PPG & 2.5 PPG STAGES. ISIP 2964 PSI. FG .73. AVG RATE 70 BPM. MAX RATE 73.7 BPM. AVG PSI 5375 PSI. MAX PSI 7329 PSI. SHUT IN WELL & TURN OVER TO WIRE LINE, 3195 BBLS FLUID TO RECOVER.
	11:00	13:30	2.50	STG02	21		P		RIH & SET 7" CBP @ 8925'. PERFORATE STAGE 2 PERFORATIONS FROM 8902' TO 8857', USING 3-1/8" TAG-RTG GUNS, 22.7 GRAM CHARGES, 3 SPF, 120 DEGREE PHASING. ALL PERFS CORRELATED TO LONE WOLF CBL/GR/CCL RUN 1 LOG DATED 04/21/2013, STARTING PRESSURE 2400 PSI, ENDING 2200 PSI, POOH W/ W.L., SHUT WELL IN & TURN OVER TO FRAC CREW
	13:30	15:00	1.50	STG02	35		P		PRESSURE TEST PUMP LINES TO 9044 PSI. OPEN WELL. SICP 2125 PSI. BREAK DOWN STAGE 2 PERFORATIONS @ 3294 PSI, PUMPING 10 BPM. BRING RATE UPTO 40 BPM. PUMP 83 TTL BBLS FLUID THEN PERFORM STEP RATE SHUT DOWN TEST. ISIP 2627 PSI. FG .73. 5 MIN 2000 PSI. 10 MIN 1918 PSI. TREAT STAGE 2 PERFORATIONS W/ 5,000 GALLONS 15% HCL ACID, 3000 LBS 100 MESH SAND IN 1/2 PPG STAGE & 24,200 LBS WHITE 30/50 SAND IN 1/2 PPG & 1 PPG EXTENDED 1 PPG STG SCREENED OUT ON 1 PPG STG 11,400#S IN PERFS & 12,800#S IN WELL BORE. ISIP 7985 PSI. AVG RATE 43.5 BPM. MAX RATE 62.2 BPM. AVG PSI 7302 PSI. MAX PSI 7985 PSI. SHUT IN WELL.
	15:00	16:00	1.00	STG02	18		N		FLUSH OUT PUMPS & PUMP LINES TO FLOW BACK TANKS
	16:00	6:00	14.00	STG02	19		N		OPEN CSG TO FLOW BACK TANKS @ 300 PSI ON 64/64 CHOKE, FLOWED BACK 171 TOTAL BBLS WATER @ 04:00
12/10/2015	6:00	7:30	1.50	STG02	28		N		CT HOLD SAFETY MTG ON WIRE LINE OPERATIONS WRITE & REVIEW JSA'S
	7:30	9:00	1.50	WLWORK	18		N		0 PSI ON WELL. RIH W/ 2-3/4" SINKER BARS TAG 7" CBP @ 8925', POOH W/ W.L. SWI & TURN WELL OVER TO FRAC
	9:00	11:00	2.00	STG02	18		N		TEST PUMP LINES TO 8990 PSI, OPEN WELL 0 PSI, ATTEMPT TO FLUSH 7" CSG PUMPED 8 BBLS WATER & PRESSURED UP TO 8000 PSI, SWI & FLUSH PUMPS & PUMP LINES W/ BRINE WTR

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
	11:00 13:00	2.00	WOR	16		N		RD WIRE LINE, & FRAC LINES FROM STACK, ND GOAT HEAD & TOP HCR VALVE, NU & TEST 5K BOP TO 4800 PSI GOOD TEST, RU WORK FLOOR & TBG TONGS
	13:00 16:00	3.00	WOR	39		N		MU & RIH W/ 6" ROCK BIT, BIT SUB, TALLY & RIN IN HOLE W/ 273 JTS 2-7/8" EUE L-80 TBG, EOT @ 8906' (BTM PERF @ 8902')
	16:00 17:15	1.25	WOR	06		N		CIRC WELL BORE W/ 350 BBLS TREATED 2% KCL
	17:15 19:30	2.25	WOR	39		N		TOOH W/ 273 JTS 2-7/8" EUE L-80 TBG, CLOSE 7" FRAC VALVE, 7" HCR VALVE & LOCK IT, CLOSE & NIGHT CAP CSG VALVES SDFN
12/11/2015	6:00 7:30	1.50	STG03	28		N		CT HOLD SAFETY MTG ON NDBOP & NUFRAC STACK WRITE & REVIEW JSA'S
	7:30 9:30	2.00	WOR	16		N		RD TBG TONGS & WORK FLOOR, ND5K BOP, NU 7" HCR, GOAT HEAD & TEST FRAC STACK TO 9500 PSI GOOD TEST
	9:30 12:30	3.00	STG03	21		P		RU WIRE LINE RIH W/ 6" OD GR/JB TO 8590', POOH, RIH W/ 7" CBP & PERF GUNS, SET 7" CBP @ 8578', PERF STG 3 PERFS 8563'-8390' USING 3-1/8" TAG RTG GUNS, 22.7 GM CHARGES @ 120 DEG PHASING, ALL PERFS CORRELATED TO THE LONE WOLF CBL/GR/CCL LOG DATED 4/21/2013, STARTING PRESSURE 900 PSI, ENDING PRESSURE 800 PSI, POOH SWI & TURN OVER TO FRAC CREW
	12:30 15:00	2.50	STG03	35		P		RU FRAC LINES TO FRAC STACK, PRESSURE TEST PUMP LINES TO 8994 PSI. OPEN WELL. SICP 389 PSI. BREAK DOWN STAGE 3 PERFORATIONS @ 2872 PSI, PUMPING 5.5 BPM. BRING RATE UPTO 40 BPM. PUMP 94 TTL BBLS FLUID THEN PERFORM STEP RATE SHUT DOWN TEST. ISIP 1790 PSI. FG .65. 5 MIN 1340 PSI. 10 MIN 1131 PSI. TREAT STAGE 3 PERFORATIONS W/ 5,000 GALLONS 15% HCL ACID, 3000 LBS 100 MESH SAND IN 1/2 PPG STAGE & 98,480 LBS WHITE 30/50 SAND IN 1/2 PPG, 1 PPG, 1.75 PPG & 2.25 PPG STAGES. ISIP 1884 PSI. FG .66. AVG RATE 74 BPM. MAX RATE 76.5 BPM. AVG PSI 2865 PSI. MAX PSI 4356 PSI. SHUT IN WELL. 3281 BBLS FLUID TO RECOVER.
	15:00 18:00	3.00	RDMO	02		P		RIG DWN & MOVE OUT FRAC & WIRE LINE EQUIPMENT
	18:00 6:00	12.00	FB	19		P		OPEN WELL TO FLOW BACK TANKS ON 12/64 CHOKE @ 1050 PSI, FLOWED 504 BBLS WATER, CURRENT PRESSURE 825 , CURRENT CHOKE 12/64
12/12/2015	6:00 7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON ND FRAC STACK WRITE & REVIEW JSA'S
	7:30 10:00	2.50	WOR	16		P		ND GOAT HEAD & TOP HCR VALVE, NU NIGHT CAP ON BTM HCR VALVE, WHILE FLOW TESTING WELL
	10:00 6:00	20.00	FB	19		P		STG 3 PERFS FLOWING BACK, CURRENT PRESSURE 850 PSI, ON 12/64 CHOKE FLOWED BACK 826 BBLS WATER
12/13/2015	6:00 6:00	24.00	FB	19		P		HOLD SAFETY MTG ON TURNING WELL TO PROD FACILITY WRITE & REVIEW JSA'S, CURRENT PSI 850 PSI FLOWED BACK 826 BLS H2O TO FLOW BACK TANK
12/14/2015	6:00 6:00	24.00	FB	19		P		HOLD SAFETY MTG ON CHANGINGG GAUGES, WRITE & REVIEW JSA'S, CURRENT PRESSURE 750 PSI, FLOWED 667 BBLS OIL, 321 BBLS WATER ON 18/64 CHOKE
12/15/2015	6:00 7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON RU WIRE LINE LUBRICATOR WRITE & REVIEW JSA'S
	7:30 10:30	3.00	WLWORK	20		P		MIRU WIRE LINE, RIH W/ 7" ARROW SET PKR W/ PUMP OUT PLUG & PLUG CATCHER, SET PKR @ 8150', POOH RD WIRE LINE
	10:30 12:30	2.00	WOR	19		P		BLOW WELL DWN RECOVERING 192 BBLS OIL & 85 BBLS WATER
	12:30 14:00	1.50	WOR	16		P		ND 7" HCR VALVE, NU & TEST 5K BOP, RU WORK FLOOR & TBG TONGS
	14:00 15:30	1.50	WOR	39		P		MU & RIH W/ 7" ON-OFF SKIRT & 251 JTS 2-7/8" TBG, LATCH ONTO PKR & SPACE OUT, J-OFF PKR, LD 2 JT 2-7/8" TBG

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
	15:30 16:30	1.00	WOR	06		P		CIRC WELL BORE W/ 300 BBLS 2% KCL & PKR FLUID
	16:30 18:30	2.00	WOR	16		P		RIH W/ 1 JT 2-7/8" TBG, WEATHERFORD BREECH LOCK TBG HANGER W/ TWO WAY VALVE, LAND TBG HANGER & LOCK IN BOWL J-OUT OF HANGER RIH & LATCH ONTO PKR, PULL UP & LAND HANGER IN BOWL IN 12K TENSION, RD TBG TONGS & WORK FLOOR, NDBOP, & 10K FRAC VALVE, NU & TEST FLOW TREE & FLOW LINES, PUMP OUT PLUG IN PKR @ 2100 PSI, TBG WENT ON VACUME
	18:30 6:00	11.50	FB	19		P		TURN WELL OVER TO FLOW BACK CREW, OPEN WELL TO FLOW BACK TANK 0 PSI, @ 21:30 WELL HAD 375 PSI & TURN TO PROD FACILITY, CURRENT PRESSURE 825 PSI ON 18/64 CHOKE, FLOWED 363 BBLS OIL & 226 BBLS WATER
12/31/2015	11:00 19:00	8.00	SL	18		P		RU SLICK LINE UNIT & HOT OIL UNITS. PRESSURE TEST ANNULUS TO 100 PSI FOR 15 MINUTES. TESTED GOOD. RIH W/ 1-1/2" SINKER BARS. TAG OBSTRUCTION @ TBG HANGER AREA, 8' FROM TOP OF WELLHEAD. ATTEMPTS TO WORK DEEPER FAILED. PUMP5 BBLS 200 DEGREE 2% KCLWTR DOWN TBG @ 800 PSI. RIH W/ 2-1/4" OD IMPRESSION BLOCK. TAG OBSTRUCTION & WORK SPANG JARS. POOH. DID NOT MARK FACE OF IMPRESSION BLOCK. SIDES OF IMPRESSION BLOCK SHOWED MARKING AS IF OBSTRUCTION TAPERED TO CENTER OF TBG. RIH W/ 1-3/4" IMPRESSION BLOCK. W/ IMPRESSION BLOCK SHOW NO MARK ON FACE & MARKING TAPERED TO CENTER OF TBG ON OUT SIDE EDGE OF BLOCK. RIH W/ WIRE TBG SCRATCHER FOR 2-7/8" TBG. TAG OBSTRUCTION. ATTEMPTS TOWORK THROUGH OBSTRUCTION FAILED. POOH. SCRATCHER HUNG UP 2' FROM TOP OF WELL HEAD. WORK FREE & POOH. COULD SEE NO DAMAGE TO SCRATCHER. RIH W/ 1-1/2" SINKER BARS TO 6000', FIGHTING HEAVY PARRIFEN TO 400'. POOH. RIH W/ 2" OD PARRIFEN KNIFE TO 6000' W/ HEAVY PARRIFEN TO 400'. POOH. WORK / 2-1/2" PARRIFEN KNIFE TO 90'. UNABLE TO WORK DEEPER. POOH. WORK 2-1/4" PARRIFEN KNIFE TO 136' UNABLE TO WORK DEEPER. POOH & SDFN
3/1/2016	6:00 7:30	1.50	MIRU	28		P		CT TGSM & JSA ( NU & TESTING BOPS )
	7:30 10:00	2.50	MIRU	01		P		RU RIG, PUMP 75 BBLS KCL DOWN TBG, ND WELL HEAD, NU AND TEST BOP, RU WORK FLOOR AND TBG EQUIPMENT.
	10:00 14:00	4.00	WOR	39		P		J BREECH LOCK HANGER, DROP DOWN J OFF PACKER, POOH L/D BREECH LOCK HANGER ASSEMBLY, RIH LATCH ON AND RELEASE 7" PACKER. POOH W/ 250 JTS 2 7/8" ON/OFF TOOL, 7" PACKER.
	14:00 18:00	4.00	WOR	39		P		RIH W/ 6" BIT, BIT SUB, 2 JTS, PSN, 261 JTS 2 7/8" TAG @ 8583' LAY DOWN 2 JTS EOT @ 8550'. INSTALL & SHUT 2 7/8" TIW VALVE W/ NIGHT CAP. SHUT AND LOCK PIPE RAMS, SHUT AND BULL PLUG CASING VALVE. RU PUMP AND RETURN LINES. CREW TRAVEL.
3/2/2016	6:00 7:30	1.50	WOR	28		P		CT TGSM & JSA ( POWER SWIVEL OPERATIONS )
	7:30 14:00	6.50	WOR	40		P		RIH W/ 2 JTS RU POWER SWIVEL ATTEMPT TO BREAK CIRCULATION W/ 1200 BBLS W/ NO SUCCESS, RD SWIVEL POOH W/ 2 7/8" TBG AND 6" BIT.
	14:00 15:30	1.50	WOR	39		P		PUMU & RIH W/ 6" BIT, BIT SUB, FLAPPER, 4' PUP JT, FLAPPER, 20 JTS 2 7/8", SAFETY JT, BAILER, 4' PERF PUP JT, 240 JTS 2 7/8". INSTALL & SHUT 2 7/8" TIW VALVE W/ NIGHT CAP. SHUT AND LOCK PIPE RAMS, SHUT AND BULL PLUG CASING VALVE.
3/3/2016	6:00 7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON RU POWER SWIVEL WRITE & REVIEW JSA'S
	7:30 8:30	1.00	WOR	24		P		0 PSI ON WELL, PU 1 JT 2-7/8" TBG, RU POWER SWIVEL, MU 1 JT 2-7/8" TBG W/ SWIVEL RIH & TAG 7" CBP @ 8578'



## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
	8:30 17:00	8.50	WOR	10		P		BEGIN DRILLING & BAILING OUT 7" CBP @ 8578', PLUG MOVING DWN HOLE, HANG UP & PUSH DWN HOLE TO 8611', FINISH DRILLING & BAILING UP 7" CBP
	17:00 18:00	1.00	WOR	24		P		RIG DWN P.S., PU & RIH W/ 6 JTS 2-7/8" TBG, TAG FILL @ 8806', POOH W/ 10 JTS 2-7/8" TBG, SHUT & LOCK PIPE RAMS, INSTALL & CLOSE TIW VALVE W/ NIGHT CAP, CLOSE & BULL PLUG CSG VALVES, DRAIN PUMP & HARD LINE, SDFN
3/4/2016	6:00 7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON MAKING CONNECTIONS W/ POWER SWIVEL, WRITE & REVIEW JSA'S
	7:30 8:30	1.00	WOR	39		P		0 PSI ON WELL, RIH W/ 9 JTS 2-7/8" TBG, RU POWER SWIVEL, MU 1 JT 2-7/8" W/ POWER SWIVEL & PUMP 50 BBLs DWN TBG
	8:30 10:30	2.00	WOR	10		P		CLEANOUT FROM 8806' TO 8887' WHEN BAILER QUIT STROKING, RIG DWN POWER SWIVEL
	10:30 12:30	2.00	WOR	39		P		SOOH W/ TBG, WHILE PUMPING DWN CSG ATTEMPTING TO FILL CSG, CSG FILLED W/ 100 BBLs, SHUT DWN TRIPPING TBG & RU TO CIRC TO RIG TANK, CIRCULATED 75 BBLs TO RIG TANK W/ GOOD CIRCULATION
	12:30 14:30	2.00	WOR	39		P		CONT TOOH W/ TBG LD, PERF SUB, FLAPPER VALVE & BAILER ASSY, TOOH W/ 20 JTS 2-7/8" TBG, F.V., 4' SUB, F.V., BIT SUB & 6" BIT, RECOVERING 10 JTS FULL OF SAND & PLUG PARTS
	14:30 16:30	2.00	WOR	39		P		MU & RIH W/ 6" ROCK BIT, BIT SUB, 2 JTS 2-7/8" TBG, 2-7/8" +45P.S.N. & 252 JTS 2-7/8" EUE L-80 TBG, EOT @ 8293', SHUT & LOCK PIPE RAMS, INSTALL & CLOSE TIW VALVE W/ NIGHT CAP, CLOSE & BULL PLUG CSG VALVES SDFN
3/5/2016	6:00 7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON USING STOP WORK AUTHORITY WRITE & REVIEW JSA'S
	7:30 8:30	1.00	WOR	39		P		0 PSI ON WELL, CONT TIH W/ 11 JTS 2-7/8" TBG & TAG @ 8648', LD 1 JT, RU POWER SWIVEL, PU 1 JT & MAKE CONNECTION W/ SWIVEL
	8:30 14:00	5.50	WOR	10		P		BREAK CIRC W/ 154 BBLs TREATED 2% KCL, CONT DRILLING OUT 7" CBP PARTS & SAND FELL THRU @ 8654', CIRC CLEAN & SWIVEL DWN & TAG @ 8887', CLEAN OUT SAND & DRILL OUT 7" CBP @ 8925', PUSH BTM OF PLUG TO LT & FINISH DRILL IT UP, CIRC CLEAN
	14:00 16:00	2.00	WOR	39		P		RD SWIVEL, TOOH W/ 275 JTS 2-7/8" TBG, P.S.N., 2 JTS 2-7/8" TBG, BIT SUB & 6" ROCK BIT
	16:00 17:30	1.50	WOR	39		P		TALLY MU & RIH W/ 4-1/8" ROCK BIT, BIT SUB, 10 JTS 2-3/8" TBG, 2-7/8" X 2-3/8" EUE X OVER & 90 JTS 2-7/8" EUE L-80 TBG, SHUT & LOCK PIPE RAMS, INSTALL & CLOSE TIW VALVE W/ NIGHT CAP, CLOSE & BULL PLUG CSG VALVES, SDFN
3/6/2016	6:00 7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON CLEAN WORK AREA WRITE & REVIEW JSA'S
	7:30 9:00	1.50	WOR	39		P		SITP 100 PSI, SICP 100 PSI, BLOW DWN WELL, CONT TIH W/ 181 JTS 2-7/8" TBG TAG FILL @ 9139'
	9:00 13:30	4.50	WOR	10		P		RU POWER SWIVEL, BREAK CIRC W/ 245 BBLs TREATED 2% KCL, CLEAN OUT FROM 9139' TO 9250' NEW PBTD, CIRC CLEAN & RIG DWN RACK OUT POWER SWIVEL
	13:30 15:30	2.00	WOR	39		P		TOOH W/ 274 JTS 2-7/8" TBG, LD 2-7/8" X 2-3/8" EUE X OVER, 10 JTS 2-3/8" TBG, BIT SUB & 4-1/8" BIT
	15:30 17:00	1.50	WOR	39		P		MU & RIH W/ 5-3/4" SOLID NO-GO, 2 JTS 2-7/8" TBG, 5-1/2" PBGA, 2' X 2-7/8" TBG SUB, 2-7/8" +45 P.S.N., 4' X 2-7/8" TBG SUB, 4 JTS 2-7/8" TBG, 7" TAC & 148 JTS 2-7/8" TBG, SHUT & LOCK PIPE RAMS, INSTALL & CLOSE TIW VALVE & NIGHT CAP, CLOSE & BULL PLUG CSG, SDFW
3/7/2016	6:00 6:00	24.00	WOR	18		P		NO ACTIVITY SDFW
3/8/2016	6:00 7:30	1.50	WOR	28		P		CT HOLD SAFETY MTG ON NDBOP & NUWH, WRITE & REVIEW JSA'S

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
	7:30 9:00	1.50	WOR	39		P		SICP 50 PSI, SITP 650 PSI, BLOW DWN WELL PUMP 25 BBLS 2% KCL DWN TBG, CONT RIH W/ 100 JTS 2-7/8" TBG, MU 6' 2-7/8" TBG SUB & TBG HANGER, SET 7" TAC @ 8105', P.S.N. @ 88243' & EOT @ 8344', TEMP LAND TBG ON HANGER
	9:00 10:00	1.00	WOR	16		P		RIG DWN TBG TONGS & WORK FLOOR, NDBOP, UNLAND TBG & LD 6' TBG SUB & TBG HANGER, MAKE UP 10K B-FLANGE & LAND TBG IN 25K TENSION, NUWH & HOOK UP FLOW LINES
	10:00 11:00	1.00	WOR	18		P		RIG DWN PEAK 2100, PICK UP LOCATION & PARK RIG ON LOCATION
	11:00 11:30	0.50	MIRU	01		P		MIRU WEATHERFORD COROD RIG
	11:30 18:30	7.00	INARTLT	03		P		PU & RIH W/ 2-1/2" X 1-3/4" X 38' ACCELERATED H.F. INSERT PUMP, 3' X 7/8" GUIDED STABILIZER SUB, ON-OFF TOOL, 1360'-16/16", 3452' 15/16", 1251' 16/16", 1066'17/16" & 1036' 18/16" COROD, CUTTING OUT & LD 2739' 15/16" COROD AS PER NEW ROD STAR, SPACE WELL OUT W/ NEW 1-1/2" X 40' POLISH ROD, SEAT PUMP, FILL TBG W/ 26 BBLS & STROKE TEST PUMP TO 1000 PS GOOD TEST, RIG DWN RIG SLIDE IN P.U. HANG OFF RODS, STROKE TEST P.U. & TURN WELL OVER TO PROD, SDFN

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> Fee
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> EP ENERGY E&P COMPANY, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1001 Louisiana, Houston, TX, 77002		<b>8. WELL NAME and NUMBER:</b> Taylor 3-9C4
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0900 FSL 1750 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWSE Section: 09 Township: 03.0S Range: 04.0W Meridian: U		<b>9. API NUMBER:</b> 43013519540000
<b>PHONE NUMBER:</b> 713 997-5138 Ext		<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: <b>8/5/2016</b>	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <span style="border: 1px solid black; padding: 2px;">Drill Out 2 Plugs</span>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
 Please see attached proposed procedure along with current and post WBD's.

Approved by the  
 August 08, 2016  
 Oil, Gas and Mining

Date: \_\_\_\_\_

By: Dark Duff

<b>NAME (PLEASE PRINT)</b> Linda Renken	<b>PHONE NUMBER</b> 713 997-5138	<b>TITLE</b> Sr. Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 8/3/2016	


## *Taylor 3-9 C4 Drillout Summary Procedure*

- POOH with rods, pump & tubing. Inspect/Repair/Re-furbish as needed. Replace any bad tubing and joints of rods.
- Pick up rock bit, and run in hole to drill up (2) 5" CBPs @ 9,275' and 9,300'. Note top perf BELOW plug is @ 9,311'. Continue cleaning out well to TD @ 11,997'.
- Pull out of hole with work string and rock bit.
- RIH w/ production tubing and rods according to WBD.
- Clean location and resume production.

**CURRENT WBD:****Current Recom Schematic**

t

Company Name: <i>EP Energy</i>	Last Updated: <i>July 13, 2016</i>
Well Name: <i>Taylor 3-9C4</i>	By: <i>Tomova</i>
Field, County, State: <i>Altamont - Bluebell, Duchesne, Utah</i>	TD: <i>11997'</i>
Surface Location: <i>Lat: 40° 13' 48.87713" N Long: 110° 20' 17.45761" W</i>	NHOW:
Producing Zone(s): <i>Wasatch</i>	PICK UP:



**PROPOSED WBD:****Proposed Recom-Drill Out Schematic**

t

Company Name: EP Energy  
 Well Name: Taylor 3-9C4  
 Field, County, State: Altamont - Bluebell, Duchesne, Utah  
 Surface Location: Lat: 40° 13' 48.87713" N Long: 110° 20' 17.45761" W  
 Producing Zone(s): Wasatch

Last Updated: July 13, 2016By: TomovaTD: 11997'

NHOW:

PICK UP:

~271 Jts 2-7/8" 6.5# N-80 8rd Tubing

**Tubing Anchor @ 8,675'**  
**4 jts 2-7/8" 6.5# L-80 8rd Tubing**  
**Seating Nipple @ 8,800'**  
**2' x 2 7/8" Tubing Sub**  
**5 1/2" x 30' PBGA**  
**2 jts 2-7/8" Mud Anchor**  
**5 3/4" No-Go Nipple**  
**EOT @ 8,900'**

9-5/8" 40# N-80 LTC @ 3,640' MD

Poor cmt 3390'-6234'

TOC @ 6234'

**Rod Detail @ 4.3 SPM**  
*\*might change based on corod replacement need*  
**1-1/2" x 40' Polished Rod**  
**1,065' - 18/16" CoRod**  
**1,088' - 17/16" CoRod**  
**1,251' - 16/16" CoRod**  
**3,452' - 15/16" CoRod**  
**1,944' - 16/16" CoRod**  
**2-1/2" x 1-3/4" x 38' Insert Pump**

TOL @ 8,994'

7" 29# HCP-110 LTC @ 9,271'

Drift I.D. - 6.059"

December '15 Recom

STG 3: 8,390' - 8,563' (19/57 holes)

5,000 gals Acid + 3,280# 100M + 98,480# 30/50

STG 2: 8,857' - 8,902' (9/27 holes)

5,000 gals Acid + 3,000# 100M + 14,400# 30/50

STG 1: 9,027' - 9,186' (21/63 holes)

5,000 gals Acid + 3,000# 100M + 90,000# 30/50

Initial Completion Perfs - Apr '13

9,311' - 9,592' (23/69 holes)

5,000 Gals 15% HCL + 140,000# 20/40

9,622' - 9,864' (23/69 holes)

5,000 Gals 15% HCL + 140,000# 20/40

9,896' - 10,109' (22/66 holes)

5,000 Gals 15% HCL + 140,000# 20/40

10,139' - 10,394' (23/69 holes)

5,000 Gals 15% HCL + 155,000# 20/40

10,418' - 10,736' (23/69 holes)

5,000 Gals 15% HCL + 155,000# 20/40

10,760' - 11,043' (23/69 holes)

5,000 Gals 15% HCL + 155,000# 20/40

11,074' - 11,444' (20/60 holes)

5,000 Gals 15% HCL + 115,000# 20/40

11,494' - 11,858' (23/69 holes)

5,000 Gals 15% HCL + 140,000# 20/40

PBD 11,892'

5" 18# P-110 STL @ 11,997'

Drift ID 4.151"

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> Fee
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> EP ENERGY E&P COMPANY, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1001 Louisiana, Houston, TX, 77002		<b>8. WELL NAME and NUMBER:</b> Taylor 3-9C4
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0900 FSL 1750 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWSE Section: 09 Township: 03.0S Range: 04.0W Meridian: U		<b>9. API NUMBER:</b> 43013519540000
<b>PHONE NUMBER:</b> 713 997-5138 Ext		<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION	<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <b>8/11/2016</b>  <input type="checkbox"/> SPUD REPORT Date of Spud:  <input type="checkbox"/> DRILLING REPORT Report Date:
OTHER: <input style="width: 100px;" type="text" value="DO Plugs"/>				

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
 EP drilled out plugs. Open perms: 8390'-9186' (2015 Recom) & 9311'-11858' (Initial Completion). Please see attached for details.

Accepted by the  
 Utah Division of  
 Oil, Gas and Mining  
**FOR RECORD ONLY**  
 October 19, 2016

<b>NAME (PLEASE PRINT)</b> Maria S. Gomez	<b>PHONE NUMBER</b> 713 997-5138	<b>TITLE</b> Consultant
<b>SIGNATURE</b> N/A	<b>DATE</b> 10/10/2016	



## CENTRAL DIVISION

ALTAMONT FIELD

TAYLOR 3-9C4

TAYLOR 3-9C4

RECOMPLETE LAND

### Operation Summary Report

Disclaimer: Although the information contained in this report is based on sound engineering practices, the copyright owner(s) does (do) not accept any responsibility whatsoever, in negligence or otherwise, for any loss or damage arising from the possession or use of the report whether in terms of correctness or otherwise. The application, therefore, by the user of this report or any part thereof, is solely at the user's own risk.

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
	7:30 9:00	1.50	WOR	39		P		SICP 50 PSI, SITP 650 PSI, BLOW DWN WELL PUMP 25 BBLS 2% KCL DWN TBG, CONT RIH W/ 100 JTS 2-7/8" TBG, MU 6' 2-7/8" TBG SUB & TBG HANGER, SET 7" TAC @ 8105', P.S.N. @ 88243' & EOT @ 8344', TEMP LAND TBG ON HANGER
	9:00 10:00	1.00	WOR	16		P		RIG DWN TBG TONGS & WORK FLOOR, NDBOP, UNLAND TBG & LD 6' TBG SUB & TBG HANGER, MAKE UP 10K B-FLANGE & LAND TBG IN 25K TENSION, NUWH & HOOK UP FLOW LINES
	10:00 11:00	1.00	WOR	18		P		RIG DWN PEAK 2100, PICK UP LOCATION & PARK RIG ON LOCATION
	11:00 11:30	0.50	MIRU	01		P		MIRU WEATHERFORD COROD RIG
	11:30 18:30	7.00	INARTLT	03		P		PU & RIH W/ 2-1/2" X 1-3/4" X 38' ACCELERATED H.F. INSERT PUMP, 3' X 7/8" GUIDED STABILIZER SUB, ON-OFF TOOL, 1360'-16/16", 3452' 15/16", 1251' 16/16", 1066'17/16" & 1036' 18/16" COROD, CUTTING OUT & LD 2739' 15/16" COROD AS PER NEW ROD STAR, SPACE WELL OUT W/ NEW 1-1/2" X 40' POLISH ROD, SEAT PUMP, FILL TBG W/ 26 BBLS & STROKE TEST PUMP TO 1000 PS GOOD TEST, RIG DWN RIG SLIDE IN P.U. HANG OFF RODS, STROKE TEST P.U. & TURN WELL OVER TO PROD, SDFN
8/6/2016	6:00 7:00	1.00	MIRU	28		P		TRAVEL TO LOCATION. HOLD SAFETY MEETING ON DAILY OPERATIONS. FILL OUT & REVIEW JSA
	7:00 8:30	1.50	MIRU	01		P		MIRU COROD RIG
	8:30 11:00	2.50	PRDHEQ	39		P		LD POLISH ROD. WORK PUMP OFF SEAT. POOH W/ 1034' # 8 COROD, 10343' # 7 COROD, 1260' # 6 COROD, 3400' # 5 COROD, 1355' #6 COROD, STABILIZER PONY ROD & PUMP.
	11:00 11:30	0.50	RDMO	02		P		RD COROD RIG
	11:30 12:30	1.00	MIRU	01		P		MIRU PEAK 1500
	12:30 14:00	1.50	PRDHEQ	16		P		ND WELL HEAD. NU BOP. PRESSURE TEST BOP TO 4000 PSI FOR 15 MINUTES
	14:00 19:00	5.00	PRDHEQ	39		P		RU TBG SCANNERS & TOOH W/ 248 JTS 2-7/8"EUE TBG, TAC, 4 JTS 2-7/8"EUE TBG, 4' X 2-7/8"EUE PUP JT, SEAT NIPPLE, 2' X 2-7/8"EUE PUP JT, 5-1/2"OD PBGA, 2 JTS 2-7/8"EUE TBG & SOLID NO/GO. ALL TBG ABOVE SEAT NIPPLE WAS SCANNED. FOUND 220 JTS YELLOW BAND, 29 JTS BLUE BAND TBG & 3 JTS RED BAND TBG, MOSTLY DUE TO ROD WEAR. RD SCANNERS. SDFN
8/7/2016	6:00 7:00	1.00	PRDHEQ	28		P		TRAVEL TO LOCATION. HOLD SAFETY MEETING ON DAILY RIG OPERATIONS. FILL OUT & REVIEW JSA
	7:00 15:00	8.00	PRDHEQ	24		P		BLEED PRESSURE OFF WELL. MU 4-1/8" OD BIT & BIT SUB. TALLY & PU 98 JTS 2-3/8"EUE TBG. CHANGE EQUIPMENT OVER TO RUN 2-7/8"EUE TBG. TIH TALLYING 176 JTS 2-7/8"EUE TBG FROM WELL. TAG @ 9250'. RU POWER SWIVEL.
	15:00 19:00	4.00	PRDHEQ	06		P		PUMP 11156 BBLS FLUID WELL DID NOT CIRCULATE. RD POWER SWIVEL. POOH W/ 26 JTS 2-7/8" EUE TBG. SDFN W/ PIPE RAMS CLOSED & LOCKED, CSG VALVES CLOSED & CAPPED & TIW VALVE INSTALLED IN TBG & CLOSED & CAPPED
8/9/2016	6:00 8:00	2.00	WOR	28		P		TRAVEL TO LKOCATION. HOLD SAFETY MEETING ON DAILEY RIG OPERATIONS. FILL OUT & REVIEW JSA
	8:00 10:00	2.00	WOR	18		P		RIG UP SECOND RIG PUMP & RUN PUMP LINES.RIH & TAG CBP @ 9275'.
	10:00 16:00	6.00	WOR	06		P		PUMP 1740 BBLS 2% KCL WTR @ 10 BPM W/ POLYMER PILLS EVERY HR TO BREAK 1/4 BPM CIRCULATION. CONTINUE PUMPING 10 BPM FOR A TTL OF 2160 BBLS. RU HOTOILER. CONTINUE PUMP W/ RIG PUMPS & HOT OILER @ 12.3 BPM. WHEN A TTL OF 2746 BBLS PUMPED WELL STARTED RETURNING 1.8 BPM
	16:00 21:00	5.00	WOR	10		P		DRILL CBP'S @ 9275', 9290' & 9300' PUMPING POLYMER PILLS AFTER DRILLING EACH CBP. CIRCULATE CLEAN. PUMPED 4687 TTL BBLS 2% KCL WTR TODAY

## 2.1 Operation Summary (Continued)

Date	Time Start-End	Duration (hr)	Phase	Activity Code	Sub	OP Code	MD from (usft)	Operation
	21:00 23:00	2.00	WOR	39		P		RD POWER SWIVEL. TOO H W/ 30 JTS 2-7/8"EUE TBG. SDFN W/ PIPE RAMS CLOSED & LOCKED, CSG VALVES CLOSED & CAPPED & TIW VALVE INSTALLED IN TBG CLOSED & CAPPED.
8/10/2016	6:00 7:00	1.00	WOR	28		P		TRAVEL TO LOCATION. HOLD SAFETY MEETING ON DAILY OPERATIONS. FILL OUT & REVIEW JSA
	7:00 12:30	5.50	WOR	39		P		TIH W/ 119 JTS 2-7/8"EUE TBG. TAG FILL @ 11813'. TOO H W/ 186 JTS 2-7/8"EUE TBG. STOPPED TO FLUSH TBG. PUMPED 4 BBLs 2% KCL WTR DOWN TBG. PRESSURE UP TO 1000 PSI
	12:30 18:00	5.50	WOR	18		P		CALL & WAIT ON CUTTERS WIRELINE UNIT TO PERFORATE TBG. RU WIRELINE UNIT. COULD NOT GET CSG COLLAR LOCATER TO FUNCTION PROPERLY. RD CUTTERS WIRELINE UNIT. WAIT ON & RU PERFORATORS WIRELINE UNIT. RIH W/ TBG PUNCHER & PERFORATE TBG @ 5640' IN JT ABOVE BIT
	18:00 20:00	2.00	WOR	39		P		TOOH W/ 77 JTS 2-7/8" EUE TBG, X-OVER & 20 JTS 2-3/8"EUE TBG. MU TBG HANGER & LAND TBG. SDFN W/ TBG HANGER IN WELLHEAD (BARRIER 1), PIPE RAMS CLOSED ON 2-7/8"EUEPUP JT SCREWED INTO TBG HANGER (BARRIER 2), (CSG VALVES CLOSED & CAPPED BARRIERS 1 & 2) & TIW VALVE INSTALLED IN TGB, CLOSED & CAPPED (BARRIER 2)
8/11/2016	6:00 7:00	1.00	WOR	28		P		TRAVEL TO LOCATION. HOLD SAFETY MEETING ON DAILY RIG OPERATIONS. FILL OUT & REVIEW JSA..
	7:00 14:00	7.00	WOR	39		P		LD 78 JTS 2-3/8"EUE TBG, BIT SUB & BIT. RU HYDROTESTER. RIH W/ SOLID NO/GO, 2 JTS 2-7/8"EUE TBG, 5-1/2"OD PBGA, 2' X 2-7/8"EUE PUP JT, SEAT NIPPLE, 4' X 2-7/8"EUE PUP JT, 4 JTS 2-7/8"EUE TBG, TAC & 266 JTS 2-7/8"EUE TBG, TESTING ALL TBG ABOVE SEAT NIPPLE TO 8500 PSI.
	14:30 15:30	1.00	WOR	16		P		RD HYDROTEST UNIT. SET TAC @ 8673' IN 20K TENSION. SN @ 8805'. EOT @ 8906'. ND BOP STACK. NU WELLHEAD.
	15:30 18:00	2.50	RDMO	02		P		RD RIG & MOVE TO THE MOON 3-32C4. MIRU COROD RIG. WELD PIN ON COROD. SDFN
8/12/2016	6:00 7:00	1.00	WOR	28		P		TRAVEL TO LOCATION. HOLD SAFETY MEETING ON DAILY RIG OPERATIONS. FILL OUT & REVIEW JSA
	7:00 13:00	6.00	WOR	39		P		TIH W/ 2-1/2" X 1-1/2" X 38' RHBC PUMP, STABILIZER ROD, BROWNING ON/OFF TOOL (NEW) & COROD, CUTTING & WELDING COROD AS NEEDED FOR ROD STAR, SPACE OUT W, 8', 6', 4' & 2' X 1" PONY RODS & 1-1/2" X 40' POLISH ROD
	14:00 15:30	1.50	WOR	18		P		FILL TBG W/ 30 BBLs 2% KCL WTR. STROKE TEST PUMP TO 1000 PSI. TESTED GOOD. RD RIG. SLIDE UNIT TURN WELL OVER TO LEASE OPERATOR